





Contract Drawings For

BOARDMAN WETLAND COMPLEX

Wetland Enhancement, Trails, Parking, and Sanitary Sewer Line Replacement.

Clackamas County Land Use Application (Not for Construction)


Project No. 1004005□

Milwaukie, Oregon □anuary, 2017

Directions to Site:

From Washington, Interstate 5 south I-5 S towards Portland At the junction with I-\(\tilde{\Pi}\)4, stay on I-5 S Take exit 300B toward U.S. 26E\(\tilde{\Pi}\)0regon 99E On US 26 follow signs for McLoughlin Boulevard Turn left onto SE Boardman Avenue Arrive at SE Boardman Avenue and Addie Street

From Salem, OR, Interstate 5 North
I-5 North towards Portland
Take exit 2□□ for I-205
Take exit 9 for OR 99E toward Downtown
Turn Right onto OR 99E NiMcLoughlin Blvd
Turn right onto SE Boardman Avenue
Arrive at SE Boardman Avenue and Addie Street



INDE OF DRAWINGS

GENERAL
G01 TITLE SHEET AND VICINIT: MAP
G02 KEI PLAN, SURVE: CONTROL, AND SHEET INDE:
G03 GENERAL NOTES, LEGEND, AND ABBREVIATIONS

(NOT INCLUDED) (NOT INCLUDED)

AREA 3 PLANTING PLAN
AREA 1 SANITAR: SEWER PLAN AND PROFILE (NOT INCLUDED)

AREA 2 SANITARI SEWER PLAN AND PROFILE (NOT INCLUDED) STREAM PROFILE

KE PLAN

GEOTECH LEGEND:

SOIL BORING LOCATION

TEST PIT LOCATION

△CP-X SURVEY CONTROL POINT

SEE NOTE 1

SURVE | NOTES:

HORICONTAL CONTROL: BASED ON NGS BENCHMARK NO. Q 723, NAD 83, 2011 OREGON NORTH ZONE.

ELEVATION DATUM:

NOTES:

1. SEE CONTRACT DOCUMENTS FOR GEOTECHINCAL DATA REPORT.

CONTROL POINT TABLE CP | NORTHING EASTING | ELEV

CP-1	37571.96	59113.64	75.24
CP-2	37249.40	58742 65	76.68
CP-3	36272.42	60309.61	74.80
CP-4	36131.82	59882.27	93.18
CP-5	36553-57	59393.18	87.82
CP-6	36756.74	59195.37	81.23
CP-7	37358.29	59109.07	73,99
CP-8	36666.73	59335.81	84,21
CP-9	36635.97	59359-85	85.55
CP-10	36685.39	59472-70	79.75
CP-11	36702 37	59542.06	76.90
CP-12	36704-10	59418.64	79.74
CP-15	37184-90	59526.50	75.87
CP-16	37226.28	59642.66	83 67

LEGEND



WETLAND TEMPORARY REMOVAL/FILL



VEGETATED CORRIDOR TEMPORARY REMOVAL/FILL

ELEVATIONS ARE BASED ON NGS
BENCHMARK NO. Q 723, ELEVATION =
102.14 FEET (NAVD 88), CONVERTED TO
98.662 (NGVD 29)


		PROJECT MANAGER	Amy Dammarell
		DESIGNED	P Woerrlein
		DRAWN BY	D Lute
		CHECKED BY	
			_
2	E		
DATE	DESCRIPTION	PROJECT NUMBER	1004005

BOARDMAN WETLAND COMPLEX

KE PLAN, SURVE CONTROL, AND SHEET INDE

FILENAME | BDMN-G02 SCALE AS SHOWN

SHEET G02





2


			PROJECT MANAGER	Amy Dammarel
			DESIGNED	P. Woerrlein
			DRAWN BY	D. Lute
			CHECKED BY	
F	- 7	Q I		
SSUE	DATE	DESCRIPTION	PROJECT NUMBER	1004005


BOARDMAN WETLAND COMPLEX


FILENAME BDMN-G03 SCALE NA

SHEET

G03









ISSUE DATE DESCRIPTION

PROJECT NUMBER 1004005

0 20 40 FILENAME BDMN-C05
SCALE AS SHOWN

SHEET C05





GENERAL NOTES:

A. PLANT LEGEND, DETAILS & INSTALLATION REQUIREMENTS - SEE SPECIFICATIONS & PLANT DETAILS

B. PLANTING SCHEDULE:

- TREES, SHRUBS, GROUNDCOVER, RUSHES & SEDGES TO BE
- INSTALLED FROM OCTOBER 1 MARCH 1ST,

 GRASS SEEDING TO BE COMPLETED FROM MARCH 1 MAY

 15TH / SEPTEMBER 1ST OCTOBER 1ST.
- C. <u>COMPOST AMENDMENT</u>: XXX C.Y. REQUIRED AT 2" DEPTH, SEE SPECS.
- D. COMPOST TOP DRESS: XXX C.Y. REQUIRED AT 4" DEPTH.
- E. <u>SECURING PLANT MATERIAL</u> PLANT MATERIALS SHALL BE SECURED 30 DAYS FROM AWARD OF CONTRACT. SUBMIT SALES ORDER AS PROOF OF PURCHASE, SEE SPECS.
- F. MYCORRHIZAL INOCULUM: MYCOAPPLY MICRONIZED ENDO / ECTO
- <u>UPLAND TREES, SHRUBS & GROUNDCOVER</u> XX LBS. AT 1 TBS PER SHRUB AND 3 TBS PER TREE (1 LB = 48 TBS)
- F. INSPECTION REQUIREMENTS: NOTIFY ENGINEER 24 HOURS IN ADVANCE. ALL SUBSEQUENT WORK SHALL BE REJECTED IF NOT REVIEWED & APPROVED.
 - TOPSOIL PREPARATION & COMPOST TYPE "A" INSTALLATION BE INSPECTED & APPROVED PRIOR TO PLANTING
 - . PLANT MATERIALS SHALL BE INSPECTED & APPROVED PRIOR TO
- PLANTING.

 LAYOUT OF PLANT MATERIALS IS TO BE INSPECTED & APPROVED PRIOR TO PLANTING.


 PLANTING.
- PLANT MATERIAL INSTALLATION SHALL BE INSPECTED & APPROVED FOR REPRESENTATIVE SAMPLE.
- G. PLANT ESTABLISHMENT PERIOD OF ONE (1) CALENDAR YEAR MINIMUM IS REQUIRED FOR ALL PLANTS INSTALLED ON THIS PROJECT AND FOR ALL PLANTING AREAS, INCLUDING THE WETLAND MITIGATION AREA. WORK SHALL INCLUDE MAINTENANCE VISITS AND MONTHLY REPORTS. MAINTENANCE SHALL INCLUDE:


 MINIMUM 36 MAINTENANCE VISITS (FEB. & NOV. @ 2 PER MONTH; MARCH—OCT. @ 4 PER MONTH)
- TEN (10) MONTHLY REPORTS
 SUBMIT WEED CONTROL PLAN FOR APPROVAL
- ALL WORK NECESSARY TO ENSURE VIGOROUS & HEALTHY GROWTH OF ALL INSTALLED PLANT MATERIALS BY WATERING, SPRAYING, PRUNING, TIGHTENING & REPAIRING OF TREE STAKES, AND RESETTING PLANTS TO PROPER GRADES OR VERTICAL
- POSITION AS REQUIRED.
 REMOVAL AND DISPOSAL OF FOREIGN, DEAD, OR REJECTED PLANT MATERIAL LEGALLY OFF—SITE & THE REPLACEMENT OF ALL UNSATISFACTORY PLANT MATERIAL INSTALLED UNDER THIS CONTRACT
- MAINTAINING A WEED-FREE CONDITION BY SPRAYING AND/OR CULTIVATING PLANTING AREAS WEEKLY AND DISPOSING OF DEAD WEEDS LEGALLY OFF—SITE.
- GENERATING & DISTRIBUTING ELECTRONICALLY A DETAILED
 MONTHLY SITE REPORT THAT RECORDS DATE, TIME, WEATHER, WORK PERFORMED, HEALTH & VIGOR OF PLANT MATERIALS, OUTSTANDING CONDITIONS WITH SUGGESTIVE CORRECTIVE
- MEASURES, & DIGITAL PHOTOS TO CAPTURE SITE PROGRESS.

 JOINT INSPECTIONS WITH PROJECT REPRESENTATIVE. THREE (3)
- CORRECTION OF ALL UNSATISFACTORY CONDITIONS WITHIN 10—DAY PERIOD UPON WRITTEN NOTICE. FAILURE TO COMPLY SHALL CONSTITUTE JUSTIFICATION BY OWNER TO TAKE CORRECTIVE STEPS & TO DEDUCT ALL COSTS FROM MONIES DUE TO CONTRACTOR.

- H. <u>WARRANTY PLANT REPLACEMENT:</u>

 THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING REPLACEMENT PLANTS FOR ALL PLANT MATERIAL REJECTED THROUGH THE FIRST YEAR OF PLANT ESTABLISHMENT.
 - ALL REJECTED PLANT MATERIAL SHALL BE REPLACED AT THE DATES APPROVED BY THE PROJECT REPRESENTATIVE. ALL REPLACEMENT PLANTS SHALL BE OF THE SAME SPECIES AND QUALITY AS THE PLANTS THEY REPLACE. SEE SPECIFICATIONS.
 - · WARRANTY ALSO APPLIES TO ALL PLANTS INSTALLED WITHIN THE WETLAND MITIGATION AREA.







GROUNDCOVERS ARCTOSTAPHYLOS UVA-URSI FRAGARIA CHILOFNSIS

PLANT LEGEND

ACER CIRCINATON

ALNUS RUBRA

ACER MACROPHYLLUM

AMELACIER ALNIFOLIA

FRAXINUS LATIFOLIA

QUERCUS GARRYANA

RHAMNUS PURSHIANA

TSUGA MERTENSIANA

SALIX LUCIDA

THUJA PLICATA

CORNUS SERICEA

BAULTHEIA SHALLON

HOLODISCUS DISCOLOR

LONICERA INVOLUCRATA

MAHONIA AQUIFOLIUM

OEMLERIA CERASIFORMIS

PHYSOCARPUS CAPITATUS

MAHONIA REPENS

RIBES SANGUINEUM

RUBUS SPECTABILIS

SYMPHORICARPOS ALBA

SAMBUCUS CAERULEA

SPIREA DOUGLASI

VACCINIUM OVATUM

VACCINIUM PARVIFOLIUM

ROSA NUTKANA

PSEUDOTSUGA MENZIESII

POPULUS TRICHOCARPA

SA	SCIRPUS ACUTUS	HARDSTEM BULRUSH
SS	CAREX OBNUPTA	SLOUGH SEDGE

COMMON NAME

RIGI FAF MAPLE

SASKATOON SERVICEBERRY

BLACK COTTONWOOD

OREGON WHITE OAK

WESTERN HEMLOCK

WESTERN RED CEDAR

REDOISER DOGWOOD

TALL OREGON GRAPE

CREEPING MAHONIA

PACIFIC NINEBARK

RED FLOWERING CURRENT

PACIFIC WILLOW

VINE MAPLE

RED ALDER

OREGON ASH

DOUGLAS FIR

CASCARA

SALAL

OCEAN SPAY

TWINBERRY

INDIAN PLUM

NOOTKA ROSE

SALMONBERRY

COMMON SNOWBERRY

EVERGREEN HUCKELBERRY

BLUE ELDERBERRY

DOUGLAS SPIREA

RED HUCKELBERRY

COSTAL STRAWRERRY

SIZE

5'-6' (3-STEM)

1-1/2" CAL

1-1/2" CAL

2" CAL

2" CAL

1" CAL.

1-1/2" CAL

1-1/2" CAL

5'

5'

1 GAL

2 GAL

2 GAL

2 GAL

2 GAL

1 GAL

2 GAL.

2 GAL

2 GAL.

1 GAL

1 GAL.

1 GAL,

1 GAL.

2 GAL.

1 GAL

1 GAL

1 GAL

1 GAL

REMOVE EXCESS SOIL TO EXPOSE ROOT FLARE & O ENSURE TOP MOST ROOT IS NO MORE THAN /2 INCH BELOW ROOT BALL SUPFACE. SEVEN EJIECLING ROOTS WHERE APPROPRIATE. SET FOOT FLARE 2 INCHES ABOVE ADJACENT BARK MULCH FINISHED GRADE (8 INCHES ABOVE OPSOIL GRADE). TRUNK FLARE SHALL BE

NETALL 4 INCH MIN. DEPTH COMPOST TOP-DHESE COVER SIDES OF ROOT BALL

SET FINISHED GRADE 1 INCH BELOW ADJUSTED CURBS & PAVILLE

INSTALL 2 INCH MIN DEPTH COMPOST

- AMENDMENT & THOROUGHLY TILL INTO EXISTING
SOIL TO 9 INCH MIN DEPTH.

INSTALL PREPARED SOIL EXCAVATED FROM HOLE AT 45 (TVP)

EXISTING SUBSOIL (TYP)

SHRUB, GROUNDCOVER & PLANTING

DETAIL NOTES:

CANTED S

-PAVING OR LAWN EDGE (TYP)

- 1 ALL GROUND COVER SHALL BE PLANTED AT EQUAL TRIANGULAR SPACING PER ON CENTER SPACING AS SPECIFIED IN PLANT LEGEND
- 3 GROUNDCOVER, RUSHES & SEDGES SPACING DETAIL



		PROJECT MANAGER	Amy Dammarell
		DESIGNED	P. Woerrlein
		DRAWN BY	D Lute
		CHECKED BY	
	(2)		
DATE	DESCRIPTION	PROJECT NUMBER	1004005B


1 TREE PLANTING DETAIL

BOARDMAN WETLAND COMPLEX

AREA 3 PLANTING PLAN

FILENAME BDMN-C08 SCALE Custom

SHEET C08



NOTES: 8 FT BOARDWALK DECK ELEVATION TO BE 72 FT.
 4 FT BOARDWALK DECK ELEVATION TO BE 30 IN ABOVE FINISHED GRADE. WETLAND BOUNDARY --100 80 D - EXISTING GROUND FINISHED GRADE ---WETLAND SECTION EXISTING GROUND 60 -100 -80 -60 -40 -20 0 20 40 60 80 100 WETLAND SECTION 4 FT BOARDWALK -FINISHED GRADE, TYP. WETLAND SECTION & STREAM CHANNEL - MATCH EXISTING GRADE, TYP. EXISTING GROUND TYPICAL CHANNEL SECTION 60 -160 -140 -120 -100 -80 -60 WETLAND SECTION PROJECT MANAGER Amy Dammarell **CROSS SECTIONS** DESIGNED P. Woerrlein DRAWN BY D. Lute **BOARDMAN WETLAND COMPLEX** SHEET FILENAME BDMN-C12


ISSUE DATE

DESCRIPTION


PROJECT NUMBER 1004005

C12

SCALE AS SHOWN








NOTES:

1. BRUSH PILE CONSTRUCTED FROM TREES AND BRUSH SALVAGED DURING DEMOLITION.


- 2. DO NOT REMOVE BARK.
- DO NOT TREAT WITH PRESERVATIVES, STAINS, OR CHEMICAL TREATMENTS.
- 4. SEE PLANTING PLAN FOR APPROX. LOCATIONS. FINAL LOCATION TO BE APPROVED BY WETLAND MITIGATION SPECIALIST.



ISSUE DATE



PROJECT NUMBER 1004005



NOTES:

- 1. HARVEST 1/2"-2" DIA. WILLOW CUTTINGS FROM LOCAL STANDS.
- 2, TIE BRANCHES INTO 36" DIA, BUNDLES ALTERNATING BUTT-ENDS, TIE SECURELY WITH TWINE,
- 3 EXCAVATE TRENCH AND PLACE BUNDLES.
- 4. PLACE 2"x4"x48" SPLIT WOOD STAKES AND LIVE WILLOW POLES THROUGH BUNDLES AT
- 5. BACKFILL WITH NATIVE SOIL, TAMP TO REMOVE ALL AIR POCKETS, MAKING SURE THAT FIRM CONTACT IS MADE BETWEEN THE LIVE WILLOW BUNDLES/STAKES AND THE SOIL.
- 6_{\odot} PLACE COIR LOGS ON UPSTREAM SIDE OF SIMULATED BEAVER DAM AND SECURE WITH STAKES SPACED AT 6' ON CENTER.
- 7. WATER BEAVER DAM AFTER INSTALLATION.

BOARDMAN WETLAND COMPLEX

SIMULATED BEAVER DAM SCALE: NTS



PROJECT MANAGER Amy Dammarell DESIGNED P. Woerrlein DRAWN BY D. Lute CHECKED BY

DESCRIPTION

RESTORATION DETAILS

FILENAME BDMN-CD01

SCALE NTS

SHEET CD01

PLANTING AREA PREPARATION
(SEE GENERAL RESTORATION PLANTING NOTES) STEP 1

APRIL 15 TO JUNE 30: CUT NOXIOUS AND UNWANTED VEGETATION TO THE GROUND AND REMOVE DEBRIS FROM SITE

STEP 2

AFTER A MINIMUM OF 12" OF RE-GROWTH, OR A MINIMUM OF ONE MONTH SPRAY REGROWTH WITH HERBICIDE

STEP 3

FOLLOWING A MINIMUM OF SIX WEEKS BUT NOT LATER THAN SEPTEMBER 15, SPOT-SPRAY RE-GROWTH WITH HERBICIDE

STEP_4

2 WEEKS MINIMUM POST SPOT-SPRAYING PLACE 3" DEPTH MEDIUM COMPOST ACCORDING TO STD SPEC SECTION XX

STEP 5

POCKET PLANT PLANTING MATERIAL THROUGH COMPOST AND INSTALL 3" DEPTH BARK OR WOOD CHIP MULCH ACCORDING TO STD SPEC SECTION XX AND THE PLANTING DETAILS. SEE NOTE 3,

NOTES:

STEP 1

1. THIS SEQUENCE OF WORK SHALL APPLY TO ALL PLANTING AREAS.

STEP_2

2, THIS DETAIL FOR ORDER OF WORK ONLY, WEED CONTROL IN PLANTING AREAS SHALL BE IN ACCORDANCE WITH STD SPEC SECTION XX.

STEP 3

STEP 4

 ${\bf 3}_{+}$ bark or wood chip mulch shall be applied to all areas except stream bank planting MIX areas. Refer to special provisions.

PLANTING AREA WEED CONTROL & SOIL PREPARATION
SCALE: NTS

STEP_5



GENERAL RESTORATION PLANTING NOTES:

- 1. ALL PLANT MATERIAL SHALL CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK STANDARDS FOR PLANT MATERIAL, CURRENT EDITION.
- 2. SEE SPECIFICATIONS FOR ADDITIONAL PLANTING AREA PREPARATION AND WEED CONTROL REQUIREMENTS. HERBICIDE APPLICATION SHALL MEET LOCAL AND STATE CODES.
- 3, IMPORTED TOPSOILS SHALL MEET THE SPECIFICATIONS OF TOPSOIL TYPE A.

PLANTING SCHEDULE:

RESTORATION MIX	COMMON NAME	SCIENTIFIC NAME	SYMBOL	SPACING	CONDITION	MIN. SIZI
SEMIPERMANENTLY						
FLOODED - TYPE 1 (EMERGENT POND FRINGE)	SMALL-FRUITED BULRUSH	SCIRPUS MICROCARPUS	(SB)	5' O.C.	CORM	2,5 FT
	BROAD LEAF ARROWHEAD	SAGITTARIA LATIFOLIA	(BA)	5' O.C.	CORM	2,5 FT
*	NARROWLEAF BUR-REED	SPARGANIUM ANGUSTIFOLIUM	(NB)	5' O.C.	CORM	2,5 FT
41	SOFT STEM BULRUSH	SCHOENOPLECTUS TABERNAEMONTANI	(SSE)	5' O.C.	PLUG	2.5 FT
SEASONALLY						
FLOODED - TYPE 2	SLOUGH SEDGE	CAREX OBNUPTA	(SS)	2' O C	PLUG	N/A
XXXXXX	LADY FERN	ATHYRIUM FILIX-FEMINA	(LF)	2' O.C.	PLUG	N/A
8888888	REDTWIG DOGWOOD	CORNUS SERICEA	(RD)	5' O.C.	1 GALLON	2,5 FT
XXXXXX	DOUGLAS SPIREA	SPIRAEA DOUGLASII	(SD)	5' O.C.	1 GALLON	2.5 FT
	PACIFIC WILLOW	SALIX LUCIDA	(SP)	5' O.C.	LIVE STAKE	2.5 FT
	SITKA WILLOW	SALIX SITCHENSIS	(SW)	5' O.C.	1 GALLON	2,5 FT
RIPARIAN – TYPE 3						
PARAM	BLACK COTTONWOOD	POPULUS BALSAMIFERA	(BC)	5' O.C.	1 GALLON	2.5 FT
	RED ALDER	ALNUS RUBRA	(RA)	5' O.C.	1 GALLON	2,5 FT
	WESTERN RED CEDAR	THUJA PLICATA	(RC)	5' O.C.	2 GALLON	5 FT
	WESTERN CRABAPPLE	MALUS FUSCA	(MF)	5' O.C.	1 GALLON	2,5 FT
	OREGON ASH	FRAXINUS LATIFOLIA	(FL)	5' O.C.	1 GALLON	2,5 FT
	SALMON BERRY	RUBUS SPECTABILIS	(SB)	5' O.C.	1 GALLON	2.5 FT
	REDTWIG DOGWOOD	CORNUS SERICEA	(RD)	5' O.C.	1 GALLON	2,5 FT
BUFFER/UPLAND - TYPE 4						
	COMMON SNOWBERRY	SYMPHORICARPOS ALBUS	(cs)	5' O.C.	1 GALLON	2.5 FT
	PACIFIC NINEBARK	PHYSOCARPUS CAPITATUS	(PN)	5' O.C.	1 GALLON	2.5 FT
	DOUGLAS FIR	PSEUDOTSUGA MENZEISII	(PM)	5' O.C.	2 GALLON	5 FT
	REDFLOWER CURRANT	RIBES SANGUINEUM	(RF)	5' O.C.	1 GALLON	2,5 FT
	VINE MAPLE	ACER CIRCINATUM	(VM)	5° 0.C.	1 GALLON	2,5 FT

PROJECT MANAGER Army Dammarell DESIGNED P Woerrlein DRAWN BY D. Lute CHECKED BY ISSUE DATE DESCRIPTION PROJECT NUMBER 1004005


PLANTING DETAILS 1

BOARDMAN WETLAND COMPLEX

FILENAME BDMN-CD02 SCALE NTS

SHEET

CD02




ISSUE DATE

DESCRIPTION

PROJECT NUMBER 1004005

SHEET CD03

FILENAME BDMN-CD03 SCALE NTS



ISSUE DATE


DESCRIPTION

PROJECT NUMBER 1004005

FILENAME BDMN-CD04

SCALE NTS


SHEET CD04



ISSUE DATE DESCRIPTION PROJECT NUMBER 1004005

FILENAME BDMN-CD05 SCALE NTS

CD05



SERVICE LATERAL NATIVE MATERIAL

NOTES:

- 1. THE SEWER TAP SHALL NOT BE MADE EXCEPT IN THE PRESENCE OF A CITY INSPECTOR NOR SHALL ANY CONNECTION BE MADE WITHOUT CITY APPROVAL.
- 2. HDPE ELECTROFUSION TEE IS REQUIRD ON HDPE SANITARY SEWER MAINLINES.
- 3. ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS".
- 4. THE TECONNECTION SHOULD NOT BE PLACED AT AN ANGLE EXCEEDING 45' FROM THE SPRINGLINE. GREATER ANGLES ARE SUBJECT TO DESIGN ENGINEER APPROVAL AND MAY REQUIRE ALTERNATE BACKFILL.
- 5 SEWER TAP SHALL BE MADE ABOVE SPRINGLINE
- 6. HOLE IN MAIN TO BE MACHINE DRILLED OR CORED.

TEE DETAIL



PROJECT MANAGER Amy Dammarell DESIGNED P Woerrlein DRAWN BY D. Lule CHECKED BY ISSUE DATE DESCRIPTION PROJECT NUMBER 1004005

SANITAR SEWER DETAILS

BOARDMAN WETLAND COMPLEX

FILENAME BDMN-CD06 SCALE NTS


SHEET

CD06

ABANDON MANHOLE DETAIL SCALE: NTS

EROSION AND SEDIMENT CONTROL PLANS:





CLASSIFICATION AND DESCRIPTION:

SITE SOIL CLASSIFICATION:

25 COVE SILT CLAY LOAM

PROPERT DESCRIPTION:

WITHIN CLACKAMAS COUNTY, TAX LOTS # 22E18CA02716, 22E18CA04101, 22E18CA04407, 22E18CA04200, 22E18CA04300, LOCATED IN SECTION 18, TOWNSHIP 2 SOUTH, RANGE 2 EAST WILLAMETTE MERIDIAN, CLACKAMAS COUNTY,

SITE DESCRIPTION:

PROJECT AREA LOCATED IN CLACKAMAS COUNTY WITHIN SENSITIVE AREAS

PROJECT LOCATION:

WETLAND BETWEEN SE BOARDMAN AVENUE AND SE JENNINGS AVENUE EAST OF SE ADDIE STREET STREET LATITUDE = 45 394 LONGITUDE= -122 611

NARRATIVE DESCRIPTIONS:

EDISTING SITE CONDITIONS

WETLAND CREEK WITH ADJACENT DEVELOPMENT

DEVELOPED CONDITIONS

REGRADE TO PROVIDE TOPOGRAPHICAL VARIETY. INSTALL BOARDWALK AND TRAILS, PROVIDE PARKING AND AMENITIES

NATURE OF CONSTRUCTION ACTIVIT AND ESTIMATED TIME TABLE

GRADING AND TRAILS (JULY 1 - DEC 15)
 COMPLETE GRADING AND SEEDING BY: DEC 15

TOTAL SITE AREA = 6.0 ACRES TOTAL DISTURBED AREA = 3.5 ACRES

RECEIVING WATER BODIES:

TRIBUTARY TO WILLAMETTE RIVER

STANDARD EROSION AND SEDIMENT CONTROL PLAN DRAWING NOTES: BMP MATRI FOR CONSTRUCTION PHASES:

- ALL PERMIT REGISTRANTS MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (SCHEDULE A 8.A)
- THE ESCP MEASURES SHOWN ON THIS PLAN ARE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS, DURING THE CONSTRUCTION PERIOD, UPGRADE THESE MEASURES AS NEEDED TO COMPLY WITH ALL APPLICABLE LOCAL STATE, AND FEDERAL EROSION AND SEDIMENT CONTROL REGULATIONS, (SCHEDULE
- AB.C.II.(1)(C))
 SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED, SUBMITTAL OF THE ESCP REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY
- REVISION TO DEQ OR AGENT. (SCHEDULE A 12.C.IV)
 PHASE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL LO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. (SCHEDULE A 8.C.IL(L)(D))
- IDENTIFY, MARK, AND PROTECT (BY FENCING OFF OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED.

IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS, (SCHEDULE AB,C.I.(1) & (2)) PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS, RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING

- PRESERVE EXISING VEGETATION THEM PRACTICAL AND RETYSCHARLE OF ARCAS, RETYSCHARL OF AN ARCAS, AND SEDMENT CONTROL MEASURES INCLUDING PERMITTER SEDIMENT CONTROL MUST BE IN PLACE BEFORE VEGETATION IS DISTURBED AND MUST REMAIN IN PLACE AND BE MAINTAINED, REPAIRED, AND PROMPTLY IMPLEMENTED FOLLOWING PROCEDURES ESTABLISHED FOR THE DURATION OF CONSTRUCTION, INCLUDING PROTECTION FOR ACTIVE STORM DRAIN INLETS AND CATCH BASINS AND APPROPRIATE NON-STORMWATER POLLUTION CONTROLS (SCHEDULE A.7.D.)
- ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK, DIRECT ALL WASH WATER INTO A PIT OR LEAK-PROOF CONTAINER, HANDLE WASH WATER AS WASTE, CONCRETE DISCHARGE TO WATERS OF THE SLATE IS PROHIBITED. (SCHEDULE A8.C.L(6) AND
- APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES AND FOR ALL ROADWAYS INCLUDING GROVEL ROADWAYS, (SCHEDULE A8.C.II,(3))

ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS. (SCHEDULE AB.C.I.(7))
PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMPS SUCH AS: GRAVELED FOR PAVED EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSTIE, OR USE AN EXIT TIRE WASH. THESE BMPS MUST BE IN PLACE PRIOR TO LAND-DISTURBING ACTIVITIES. (SCHEDULE A 7.D.II. AND A8.C.(4))

- WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE. (SCHEDULE A.T.D.II.(5))
 USE BMPS TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANTS FROM SPILLS: VEHICLE AND EQUIPMENT FUELING, MAINTENANCE, AND STORAGE; OTHER CLEANING AND MAINTENANCE ACTIVITIES: AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, LEFTOVER PAINTS, SOLVENTS, AND GLUES FROM CONSTRUCTION OPERATIONS. (SCHEDULE A.7.E.L.(2))
- 14. IMPLEMENT THE FOLLOWING BIMPS WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KTS IN ALL VEHICLES, REQUIAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. (SCH A 7.E.III.)

- 15, USE WATER, SOIL-BINDING AGENT OR OTHER DUST CONTROL TECHNIQUE AS NEEDED TO AVOID WIND-BLOWN SOIL (SCHEDULE A 7.A.N)
 16, THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES
- TO SURFACE WATERS EXERCISE CAUTION WHEN USING TIME-RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN ZONE. (SCHEDULE A.9.B.III)

 17. IF A STORMWATER TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM, LOCATION AL INLET, LOCATION OF DISCHARGE, DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM, OBTAIN PLAN

APPROVAL BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (SCHEDULE A9.D) TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT

SOILS ARE STABLE DURING RAIN EVENTS AT ALL LIMES OF THE YEAR, (SCHEDULE A 7.A.II) AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMPS MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO

SURFACE WATERS OR CONVEYANCE SYSTEMS LEADING TO SURFACE WATERS. (SCHEDULE A 7.E.II.(2)) CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE EXCAVATION AND CREATION OF BARE GROLIND DURING WET WEATHER. (SCHEDULE AZ.A.I.)

SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL. (SCHEDULE A.9.C.I)

22. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE GROUND HEIGHT AND BEFORE BMP REMOVAL, (SCHEDULE A9.C.II) 23. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT, SEDIMENT BASINS AND SEDIMENT TRAPS: REMOVE TRAPPED

SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION PROJECT, CSCHIDULE AS, 2C. LIKE VI. SEDIMENT SEDIMENT BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION OF PROJECT, CSCHEDULE AS, 2C. LIKE VI. SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE MUST BE REMEDIATED, INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS, ANY IN-STREAM CLEAN UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DIVISION OF STATE LANDS REQUIRED TIMEFRAME, (SCHEDULE AS,B.)

25. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP

MUST BE USED TO CLEANUP RELEASED SEDIMENTS. (SCHEDULE A9.B.II)

26. THE ENTIRE SITE MUST BE TEMPORARILY STABILIZED USING VEGETATION OR A HEAVY MULCH LAYER, TEMPORARY SEEDING, OR OTHER METHOD SHOULD ALL CONSTRUCTION ACTIVITIES CEASE FOR 3D DAYS OR MORE. (SCHEDULE A.7.F.I)
PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF

BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR ON ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE. (SCHEDULE A7.F.II)
28. PROVIDE PERMANENT EROSION CONTROL MEASURES ON ALL EXPOSED AREAS, DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT

VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. HOWEVER, DO REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AS EXPOSED AREAS BECOME STABILIZED, UNLESS DOING SO CONFLICTS WITH LOCAL REQUIREMENTS, PROPERLY DISPOSE OF CONSTRUCTION MATERIALS AND WASTE, INCLUDING SEDIMENT RETAINED BY TEMPORARY BROSS CONFLICTS WITH LOCAL REQUIREMENTS, PROPERLY DISPOSE OF CONSTRUCTION MATERIALS AND WASTE, INCLUDING SEDIMENT RETAINED BY TEMPORARY BMPS, (SCHEDULE A.7.A.V(2) AND AB.C.III)

29. IF WATER OF THE STATE IS WITHIN THE PROJECT SITE OR WITHIN 50 FEET OF THE PROJECT BOUNDARY, MAINTAIN THE EXISTING NATURAL BUFFER AND PROVIDE ADDITIONAL PROPRIED FOR THE DURATION OF THE PERMIT COVERAGE, OR MAINTAIN LESS THAN THE ENTIRE EXISTING NATURAL BUFFER AND PROVIDE ADDITIONAL

EROSION AND SEDIMENT CONTROL BMPS. (SCHEDULE A.7.B.I)

LOCAL AGENC -- SPECIFIC EROSION CONTROL NOTES:

- 1. IF VEGETATIVE SEED MIXES ARE SPECIFIED, SEEDING MUST TAKE PLACE NO LATER THAT SEPTEMBER 1; THE TYPE AND PERCENTAGES OF SEED IN THE MIX
- MUST BE IDENTIFIED ON THE PLANS,
 ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE DISCHARGED OVER AN UNDISTURBED, PREFERABLY VEGETATED AREA, AND THROUGH A SEDIMENT CONTROL
- 3. ALL EXPOSED SOILS MUST BE COVERED DURING THE WET WEATHER PERIOD (OCT 1 MAY 31).

PLANNING ENGINEERING SURVESING FIRM:

DEVELOPER:

OAK LODGE WATER SE CONTACT: JASON RICE 14496 SE RIVER ROAD OAK GROVE, OR 97267 PHONE: 503-654-7765

ENGINEERING:

HDR ENGINEERING, INC CONTACT: AMY DAMMARELI 1001 SW 5TH AVENUE, SUITE 1800 PORTLAND, OR 97204-1134 PHONE: 503-423-3700 FAX: 503-423-3737

SURVEDING FIRM:

AKS ENGINEERING AND FORESTRY CONTACT: NICK WHITE 12965 SW HERMAN ROAD #100 PHONE: 503-563-6151

REFER TO DEQ GUIDANCE MANUAL FOR A COMPREHENSIVE LIST OF AVAILABLE BMPS

	CLEARING	MASS GRADING	UTILITY INSTALLATION	STREET CONSTRUCTION	FINAL STABILIZATION	WET WEATHER (OCT 1 - MAY 31
EROSION PREVENTION						
PRESERVE MAJURAL VEILETATION	reg	- 1			X	1
CHOUND COVER	X.		x		7.1	100
HYDRUUUG APPLICATIONS					T	
PLASTIC DATETING						
MATTING						
bust compl.	¥	¥			X	
TEMPORARY/ PERMANENT SEEDING		X	X		x	(X)
DUFFER ZORE	*100	×			Y	1
OTHER FLOW DIMERSION		*%	X			
SEDIMENT CONTROL						
SCHWOIT FINCE (PERMETER)					¥	Y
SEEMENT FORCE (NTERIOR)	erg.	- X		180	1	
STRAIT WATTLES				1.00	¥	
FILTER BERM	***	7.			X	Y
DEST PROTECTION	***		:X	(00)		
DEWATERING	193	×	x			
SEDMENT TRAP	47%		X			
NATURAL BUFFER ENCROACHMENT						
GTHER						
RUN OFF CONTROL						
CONSTRUCTION ENTRUMET	ery	X	- X	1	×	- X
PIPE SLOPE DRUM						
OUTLET PROJECTION	***		×		×	
SURFACE HOUGHERING					¥	¥
DISCH DIME	x	*				
OTHER						
POLLUTION PREVENTION						
PROPER SQUACE	χ.	- X	- 3	N.	×	- X-
INS WATE MENT			¥			
SPAIL KIT ON-SHE	***	1	×	- 1		
CONCRETE WASHOUT AREA			×	N.		
OTHO:						

SIGNIFIES BMP THAT WILL BE INSTALLED PRIOR TO ANY GROUND DISTURBING ACTIVITY

RATIONALE STATEMENT:

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP) OPTIONS BASED ON DEG'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED BMPS WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS, INCLUDING SOIL CONDITIONS TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS, AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN, AN ACTION PLAN WILL BE SUBMITTED.

INITIAL PERMITTEE'S SITE INSPECTOR: COMPANY/AGENCY: PHONE: FAX F-MAIL: DESCRIPTION OF EXPERIENCE:

INSPECTION FREQUENCY:

SITE CONDITION	MINIMUM FREQUENCY			
1. ACTIVE PERIOD	DAILY WHEN STORMWATER RUNOFF, INCLUDING RUNOFF FROM SNOW MELT, IS OCCURRING. AT LEAST ONCE EVERY FOURTEEN (14) CALENDA DAYS, REGARDLESS OF WHETHER RUNOFF IS OCCURRING.			
2. PRIOR TO THE SITE BECOMING INACTIVE OR IN ANTICIPATION OF SITE INACCESSIBILITY.	ONCE TO ENSURE THAT EROSION AND SEDIMENT CONTROL MEASURES ARE IN WORKING ORDER. ANY NECESSARY MAINTENANCE AND REPAIR MUST BE MADE PRIOR TO LEAVING THE SITE.			
3. INACTIVE PRIOR GREATER THAN FOURTEEN (14) CONSECUTIVE CALENDAR DAYS.	ONCE EVERY 1 MONTH			
PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER.	IF PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT AND ACCESSIBLE DISCHARGE POINT OR DOWNSTREAM LOCATION.			
5 PERIOD DURING WHICH DISCHARGE IS UNLIKELY DUE TO FREEZING CONDITIONS.	MONTHLY, RESUME MONITORING IMMEDIATELY UPON MELT, OR WHEN WEATHER CONDITIONS MAKE DISCHARGE UNLIKELY.			

- HOLD A PRE-CON MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE FC INSPECTOR. ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200C PERMIT REQUIREMENTS.
- INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200C PERMIT REQUIREMENTS
- RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ. AGENT, OR LOCAL MUNICIPALITY DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE
- CALENDAR DAYS, RETAIN THE ESCP AT THE CONSTRUCTION SITE OR AT ANOTHER LOCATION (SCHEDULE B.2.a)

GENERAL NOTE:

THE PERMITTEE IS REQUIRED TO MEET ALL THE CONDITIONS OF THE 1200C PERMIT. THIS ESCP AND GENERAL CONDITIONS HAVE BEEN DEVELOPED TO FACILITATE COMPLIANCE WITH THE 1200C PERMIT REQUIREMENTS. IN CASES OF DISCREPANCIES OR OMISSIONS, THE 1200C PERMIT REQUIREMENTS SUPERCEDE REQUIREMENTS OF THIS PLAN.

ATTENTION E□CAVATORS:

OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN 0AR 952-001-0010 THROUGH 0AR 952-001-0090, YOU MAY OBTAIN COPIES OF THESE RULES FROM THE CENTER BY CALLING 503-232-1987. IF YOU HAVE ANY QUESTIONS ABOUT THE RULES, YOU MAY CONTACT THE CENTER TOU MUST NOTIFY THE CENTER AT LEAST TWO BUSINESS DAYS BEFORE COMMENCING AN EXCANATION. CALL

PROJECT MANAGER Amy Dammarell DESIGNED P Woerrlein DRAWN BY D. Lute CHECKED BY ISSUE DATE DESCRIPTION PROJECT NUMBER 1004005


BOARDMAN WETLAND COMPLEX

EROSION AND SEDIMENT CONTROL GENERAL NOTES

> FILENAME | BDMN-ECO: SCALE AS SHOWN

SHEET

EC01





BOARDMAN WETLAND COMPLEX


EROSION AND SEDIMENT CONTROL PLAN


FILENAME BDMN-EC02

SCALE AS SHOWN

EC02

SHEET





ISSUE DATE

DESCRIPTION

PROJECT NUMBER 1004005

FILENAME BDMN-EC04 SCALE AS SHOWN

EC04