



Appendix D. WETS Table

USDA Field Office Climate Data

WETS Station : OREGON CITY, OR6334 Creation Date: 09/13/2016
 Latitude: 45.21 Longitude: 122.36 Elevation: 00167
 State FIPS/County(FIPS): 41005 County Name: Clackamas
 Start yr. - 1971 End yr. - 2000

| Month | Temperature (Degrees F.) | | | Precipitation (Inches) | | | | |
|-----------|-----------------------------|---------------------|------|---------------------------|-------------------------|--------------|---|----------------------|
| | avg daily max | avg daily min | avg | avg | 70% chance will have | | avg # of days w/ 11 or fall more | avg total snow |
| | | | | | less than | more than | | |
| January | 47.9 | 35.7 | 41.8 | 6.59 | 4.22 | 7.94 | 13 | 0.6 |
| February | 52.8 | 37.3 | 45.1 | 5.51 | 3.89 | 6.56 | 12 | 1.2 |
| March | 58.0 | 39.7 | 48.9 | 4.70 | 3.54 | 5.49 | 10 | 0.0 |
| April | 63.4 | 42.5 | 53.0 | 3.46 | 2.44 | 4.10 | 9 | 0.0 |
| May | 70.0 | 47.6 | 58.8 | 2.70 | 1.72 | 3.26 | 7 | 0.0 |
| June | 75.8 | 52.1 | 64.0 | 1.83 | 1.11 | 2.22 | 5 | 0.0 |
| July | 82.6 | 56.0 | 69.3 | 0.83 | 0.29 | 1.00 | 2 | 0.0 |
| August | 83.0 | 56.1 | 69.6 | 1.00 | 0.21 | 1.16 | 3 | 0.0 |
| September | 77.7 | 52.1 | 64.9 | 1.93 | 0.86 | 2.41 | 4 | 0.0 |
| October | 65.9 | 45.6 | 55.8 | 3.48 | 1.85 | 4.25 | 8 | 0.0 |
| November | 53.4 | 40.2 | 46.8 | 6.79 | 4.43 | 8.16 | 13 | 0.1 |
| December | 47.0 | 35.9 | 41.5 | 7.23 | 4.85 | 8.65 | 13 | 0.6 |
| Annual | | | | | 40.45 | 50.63 | | |
| Average | 64.8 | 45.1 | 55.0 | | | | | |
| Average | | | | 46.05 | | | 98 | 1.7 |

GROWING SEASON DATES

| Probability | Temperature | | |
|-------------|---|--------------------------|---------------------------|
| | 24 F or higher | 28 F or higher | 32 F or higher |
| | Beginning and Ending Dates Growing Season Length | | |
| 50 percent | 1/25 to 11/7 346 days | 2/15 to 12/4 292 days | 3/24 to 11/11 232 days |
| 70 percent | > 365 days > 365 days | 2/7 to 12/12 307 days | 3/15 to 11/19 248 days |



WETS Table

* Percent change of the growing season occurring between the Beginning and Ending dates.

Total 1911-2016 precip

Station : OR6334, OREGON CITY
----- Unit = inches

| yr | jan | feb | mar | apr | may | jun | jul | aug | sep | oct | nov | dec | annl |
|----|-------|-------|-------|------|-------|------|-------|------|------|-------|--------|--------|-------|
| 11 | | | | | | | | | | | 3.49 | 4.82 | 8.31 |
| 12 | 9.10 | 5.27 | 2.15 | 2.89 | 2.17 | 4.12 | 0.61 | 5.16 | 1.26 | 4.19 | 6.71 | 7.11 | 50.74 |
| 13 | 8.18 | 1.28 | 5.79 | 4.11 | 2.36 | 4.23 | 0.67 | 0.74 | 3.01 | 4.50 | 7.50 | 3.79 | 46.16 |
| 14 | 12.79 | 5.07 | 4.07 | 4.26 | 2.11 | 3.55 | 0.17 | 0.00 | 3.85 | 4.50 | 5.07 | 3.16 | 47.60 |
| 15 | 6.14 | 4.40 | 2.83 | 2.11 | 2.78 | 1.64 | 1.44 | 0.00 | 0.67 | 2.11 | M11.04 | 19.24 | 47.50 |
| 16 | 6.44 | 11.47 | 12.06 | 4.21 | 3.09 | 1.86 | 2.90 | 0.26 | 1.95 | 1.64 | 8.18 | 4.40 | 58.41 |
| 17 | 4.21 | 3.72 | 8.22 | 6.97 | 3.67 | 1.48 | 0.01 | 0.00 | 2.24 | 0.03 | 4.23 | 18.71 | 53.49 |
| 18 | 6.40 | 8.06 | 5.50 | 1.22 | 1.16 | 0.01 | 0.67 | 0.74 | 0.38 | 5.07 | 5.06 | 4.99 | 39.26 |
| 19 | 10.91 | 8.96 | 6.01 | 4.42 | 2.56 | 1.04 | 0.08 | 0.05 | 3.91 | 1.73 | 9.73 | 6.79 | 58.17 |
| 20 | 5.84 | 0.40 | 4.36 | 5.61 | 1.25 | 3.03 | 1.18 | 1.39 | 5.76 | 5.01 | 7.18 | 9.79 | 50.80 |
| 21 | 8.92 | 7.67 | 5.34 | 2.17 | 2.06 | 1.50 | 0.03 | 0.16 | 2.89 | 3.30 | 12.12 | 3.32 | 49.90 |
| 22 | 4.04 | 4.24 | 7.83 | 2.94 | 1.24 | 0.23 | 0.00 | 2.26 | 1.86 | 5.03 | 2.66 | 9.87 | 42.20 |
| 23 | 13.00 | 2.55 | 1.14 | 2.10 | 1.68 | | | | | 0.38 | 4.77 | 7.00 | 34.62 |
| 24 | 3.27 | 5.87 | 1.93 | 1.24 | | | | | | 6.58 | 8.29 | 5.10 | 32.28 |
| 25 | 8.80 | 8.87 | 2.94 | 3.81 | | | | | | 0.05 | 5.71 | 5.55 | 35.73 |
| 26 | 3.46 | | 1.01 | 1.50 | | | | | | 5.01 | 9.93 | 5.39 | 26.30 |
| 27 | 8.67 | 8.11 | 3.65 | 1.50 | | | | | | 4.47 | 10.19 | 2.86 | 39.65 |
| 28 | 5.63 | 1.76 | 8.96 | 6.00 | | | | | | 1.92 | 6.26 | 8.72 | 39.25 |
| 29 | 3.50 | 1.24 | 3.27 | 4.37 | | | | | | 1.29 | 0.70 | 11.34 | 25.71 |
| 30 | 4.40 | 6.81 | 2.07 | 3.12 | | | | | | 2.49 | 3.05 | 3.13 | 28.07 |
| 31 | M3.29 | 3.07 | 6.00 | 4.60 | | | | | | 5.42 | 8.22 | 9.15 | 40.45 |
| 32 | 6.41 | M3.69 | 8.25 | 3.81 | | | | | | 4.83 | 9.41 | 6.82 | 43.16 |
| 33 | 8.48 | 4.49 | 6.23 | 1.01 | | | | | | | | | 20.21 |
| 34 | | | | | | | | | | | | | |
| 35 | | | | | | | | | | | | | |
| 36 | | | | | | | | | | | | | |
| 37 | | | | | | | | | | | | | |
| 38 | | | | | | | | | | | | | |
| 39 | | | | | | | | | | | | | |
| 40 | | | | | | | | | | | | | |
| 41 | | | | | | | | | | | | | |
| 42 | | | | | | | | | | | | | |
| 43 | | | | | | | | | | | | | |
| 44 | | | | | | | | | | | | | |
| 45 | | | | | | | | | | | | | |
| 46 | | | | | | | | | | | | | |
| 47 | | | | | | | | | | | | | |
| 48 | M0.17 | 7.57 | 4.70 | 4.27 | 4.73 | 1.15 | 0.91 | 2.07 | 3.46 | 2.70 | 0.46 | M10.26 | 50.45 |
| 49 | 1.46 | 13.09 | 3.34 | 1.16 | 2.69 | 1.25 | 0.94 | 0.22 | 2.60 | 3.17 | 6.92 | 6.50 | 43.36 |
| 50 | 11.44 | M6.97 | M6.09 | 3.13 | 1.09 | 2.05 | 1.35 | 0.45 | 2.26 | 10.34 | 12.70 | 7.48 | 65.55 |
| 51 | 10.50 | 5.93 | 5.63 | 1.06 | 2.50 | 0.09 | 0.16 | 0.34 | 3.71 | 5.55 | 6.25 | 7.25 | 49.09 |
| 52 | 6.20 | 4.72 | 4.51 | 1.75 | 0.99 | 3.30 | 0.00 | 0.09 | 0.42 | 0.87 | 1.32 | 1.70 | 31.77 |
| 53 | 16.77 | 4.76 | 4.96 | 2.52 | M4.35 | 1.50 | 0.04 | 2.53 | 1.40 | 3.39 | 7.46 | 9.04 | 58.52 |
| 54 | 11.25 | 5.06 | 3.46 | 5.88 | 2.17 | 3.76 | 0.69 | 2.18 | 1.01 | 3.91 | 5.61 | 6.49 | 49.47 |
| 55 | 3.02 | 3.62 | 5.32 | 6.30 | 1.45 | 1.37 | 1.39 | 0.00 | 3.46 | 7.68 | 9.71 | 11.20 | 54.52 |
| 56 | 14.25 | 4.44 | 7.61 | 6.68 | 2.30 | 1.99 | 0.02 | 3.57 | 1.67 | 7.69 | 1.81 | 4.53 | 50.56 |
| 57 | 3.26 | 4.81 | 0.43 | 1.06 | 3.10 | 1.95 | M0.43 | 0.37 | 0.68 | 3.97 | 4.92 | M10.60 | 44.20 |
| 58 | 3.43 | 6.93 | 2.67 | 5.38 | 0.61 | 3.26 | 0.00 | 0.04 | 1.40 | 1.73 | 8.21 | 7.12 | 46.78 |
| 59 | 10.41 | 5.75 | 5.07 | 1.65 | 3.76 | 2.00 | 0.83 | 0.17 | 3.81 | 4.17 | 3.34 | 3.86 | 44.82 |
| 60 | 4.91 | 4.94 | 6.84 | 4.09 | 5.80 | 0.64 | 0.00 | 1.32 | 1.20 | 3.49 | 12.68 | 4.18 | 49.90 |


WETS Table

| | | | | | | | | | | | | | |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|--------|--------|-------|
| 61 | 5.22 | 11.74 | 7.01 | 5.47 | 4.14 | 0.60 | 0.57 | 0.85 | 0.84 | 4.04 | 6.01 | 6.65 | 51.14 |
| 62 | 2.13 | 4.33 | 5.88 | 4.05 | 3.62 | 1.15 | 0.06 | 1.37 | 2.43 | 4.36 | 11.78 | 3.00 | 44.16 |
| 63 | 1.96 | 4.99 | 6.33 | 5.06 | 4.36 | 1.74 | 1.30 | 0.54 | 1.46 | 3.68 | 7.73 | 4.22 | 43.37 |
| 64 | 3.64 | 1.22 | 4.43 | 1.85 | 1.07 | 2.90 | 0.76 | 0.95 | 1.72 | 1.22 | 9.65 | 14.78 | 54.19 |
| 65 | 10.67 | 1.99 | 1.47 | 3.42 | 1.91 | 0.75 | 0.24 | 1.50 | 0.03 | 2.54 | 7.28 | 8.87 | 40.67 |
| 66 | 9.75 | 2.19 | 6.43 | 1.29 | 1.31 | 1.67 | 1.28 | 0.31 | 1.72 | 3.32 | 6.60 | 8.29 | 44.14 |
| 67 | 8.65 | 2.76 | 6.08 | 3.54 | 2.52 | 1.17 | 0.00 | 0.00 | 0.81 | 6.36 | 2.74 | 16.24 | 40.87 |
| 68 | 5.53 | 8.87 | 3.60 | 1.95 | 3.23 | 3.44 | 0.50 | 4.95 | 3.83 | 7.09 | 7.89 | 14.58 | 65.44 |
| 69 | 10.47 | 3.92 | 2.99 | 9.44 | 2.23 | 4.48 | 0.09 | 0.11 | 4.50 | 5.00 | 3.77 | 9.15 | 56.15 |
| 70 | 14.05 | 6.09 | 3.01 | 9.76 | 1.81 | 0.69 | 0.09 | 0.00 | 2.15 | 3.59 | 8.69 | 9.36 | 53.23 |
| 71 | 10.06 | 4.50 | 6.27 | 4.33 | 2.41 | 3.16 | 0.37 | 1.50 | 3.79 | 4.57 | 7.66 | 10.25 | 56.69 |
| 72 | 9.17 | 6.71 | 6.53 | 4.81 | 2.87 | 0.73 | 0.50 | 0.71 | 4.41 | 1.04 | 6.47 | 9.79 | 53.74 |
| 73 | 5.90 | 2.34 | 4.00 | 1.79 | 1.62 | 2.23 | 0.08 | 1.40 | 3.18 | 14.00 | 14.21 | 11.93 | 52.68 |
| 74 | 9.57 | 6.70 | 8.04 | 2.81 | 2.63 | 1.18 | 2.82 | 0.06 | 0.40 | 2.44 | 7.21 | 6.87 | 50.73 |
| 75 | 8.28 | 5.51 | 5.67 | 5.44 | 1.94 | 2.12 | 0.74 | 3.41 | 0.00 | 6.25 | 5.54 | 7.79 | 49.56 |
| 76 | 6.33 | 8.11 | 3.64 | 13.55 | 7.12 | 0.67 | 0.87 | 2.30 | 1.25 | 1.20 | 0.98 | 1.69 | 32.66 |
| 77 | 1.65 | 3.52 | 4.20 | 0.77 | 4.31 | 1.41 | 0.68 | 3.01 | 4.41 | 2.82 | 17.17 | 11.49 | 44.54 |
| 78 | 5.96 | 4.53 | 1.88 | 5.84 | 4.45 | 1.71 | 1.53 | 2.36 | 2.88 | 0.61 | 4.73 | 3.27 | 39.75 |
| 79 | 2.90 | 8.99 | 3.30 | 3.94 | 2.49 | 0.70 | 0.52 | 0.98 | 13.14 | 5.70 | 3.75 | 7.73 | 44.14 |
| 80 | 11.38 | 4.38 | 3.71 | 3.91 | 1.30 | 3.79 | 0.18 | 0.22 | 1.65 | 1.56 | 7.60 | 12.61 | 52.29 |
| 81 | 1.84 | 4.51 | 7.13 | 2.55 | 1.83 | 4.52 | 0.28 | 0.00 | 2.84 | 4.79 | 5.49 | 11.42 | 43.20 |
| 82 | 7.75 | M8.22 | 5.18 | 4.37 | 1.66 | 1.05 | 0.22 | 1.27 | 3.76 | 4.25 | 5.42 | 10.39 | 53.55 |
| 83 | 8.70 | 8.99 | 7.87 | 2.50 | 2.11 | | 4.24 | 2.57 | M0.53 | 2.16 | 9.82 | 6.78 | 56.21 |
| 84 | 3.29 | 5.53 | | 3.82 | 5.19 | 4.60 | 0.00 | 0.03 | | 6.24 | 12.34 | 4.27 | 45.71 |
| 85 | 0.46 | M3.64 | 4.39 | 1.38 | 0.92 | M2.51 | 0.43 | 0.52 | 2.65 | 3.59 | 6.47 | M3.05 | 30.02 |
| 86 | M6.56 | 7.99 | 3.19 | 2.40 | M2.89 | 0.57 | 1.92 | M0.00 | M0.93 | M2.08 | M6.93 | | 35.46 |
| 87 | 7.92 | 4.44 | 6.00 | 2.71 | M2.11 | M0.49 | M1.62 | 0.23 | 0.84 | 0.29 | 2.25 | M10.77 | 39.67 |
| 88 | 9.17 | 2.04 | 4.91 | 5.85 | M3.58 | 1.94 | 0.59 | 0.08 | M1.51 | 0.18 | 11.24 | 3.43 | 44.52 |
| 89 | 5.18 | 3.18 | M7.08 | 2.02 | M2.23 | 1.05 | 0.58 | 1.45 | 1.10 | M2.25 | 3.69 | 3.98 | 33.79 |
| 90 | M9.65 | M4.58 | 2.78 | 2.59 | M1.92 | M2.46 | 0.48 | 1.00 | 0.47 | M5.94 | 4.94 | 3.31 | 40.12 |
| 91 | 3.50 | 4.26 | 3.71 | 4.63 | 4.40 | 2.32 | 0.06 | 1.61 | 0.15 | 2.98 | 7.65 | 5.99 | 41.26 |
| 92 | 5.24 | 4.40 | 1.12 | 5.10 | 0.16 | 0.41 | 0.26 | 0.76 | 1.86 | 4.19 | 4.46 | M6.51 | 34.55 |
| 93 | 3.74 | 1.11 | M5.24 | 6.15 | 4.24 | M1.73 | M2.23 | M0.23 | 0.00 | M1.43 | 1.91 | M6.48 | 34.49 |
| 94 | M5.38 | M6.33 | 4.12 | 2.14 | 1.71 | 1.53 | 0.08 | 0.00 | 1.10 | M7.22 | M8.74 | 6.62 | 44.97 |
| 95 | 7.61 | 5.44 | 4.23 | 3.08 | 1.54 | M1.97 | 0.76 | 1.62 | M2.93 | 4.02 | M11.00 | M8.36 | 54.16 |
| 96 | 9.17 | 12.05 | 3.86 | 5.53 | M5.00 | 0.91 | 0.63 | 0.11 | M2.25 | M5.33 | M9.96 | M16.13 | 71.03 |
| 97 | M8.45 | M2.20 | 6.63 | 4.91 | M2.37 | M2.38 | 1.01 | 1.54 | 4.02 | M5.70 | M3.97 | 3.47 | 48.65 |
| 98 | M8.91 | M4.86 | 4.68 | M1.19 | 4.99 | M1.03 | 0.43 | 0.02 | 1.13 | M4.21 | 11.32 | 9.74 | 52.51 |
| 99 | 9.14 | 10.01 | 5.60 | 3.43 | 3.41 | 1.78 | 0.20 | 0.84 | 0.19 | M2.70 | | M5.01 | 42.31 |
| 00 | M4.06 | M6.29 | M3.08 | M2.26 | M2.25 | M1.41 | M0.46 | 0.02 | M0.48 | M3.88 | M2.50 | M2.90 | 31.47 |
| 01 | M1.25 | M1.33 | M5.02 | M2.62 | 1.60 | M1.61 | M0.73 | 1.05 | M0.80 | M2.65 | M6.52 | M9.54 | 34.92 |
| 02 | M8.03 | 3.90 | M5.55 | M3.58 | M1.50 | M2.09 | 0.37 | 0.29 | M0.49 | 0.47 | M2.81 | M10.18 | 40.12 |
| 03 | M7.60 | M3.00 | M7.05 | M5.58 | M0.52 | M0.70 | 0.00 | | 1.02 | M3.02 | M6.20 | 9.30 | 45.74 |
| 04 | M5.98 | 0.00 | | M1.74 | M2.38 | 2.15 | 0.15 | 3.20 | M2.27 | M5.62 | 1.89 | 4.35 | 33.06 |
| 05 | M2.26 | 0.78 | M5.43 | M3.13 | M4.57 | M2.06 | 0.57 | M0.50 | M1.58 | M3.19 | M6.91 | 9.91 | 40.80 |
| 06 | M3.20 | M2.90 | M4.17 | 6.28 | | 1.01 | M0.09 | M0.06 | M1.75 | M1.59 | M12.41 | M2.34 | 45.00 |
| 07 | M1.01 | M2.13 | M1.69 | M1.59 | 0.61 | M0.49 | M0.32 | 0.00 | 0.32 | M6.14 | M5.90 | M9.50 | 29.70 |
| 08 | M7.92 | M3.53 | M6.13 | M0.30 | | M1.44 | | M1.53 | M0.45 | | M7.34 | M3.43 | 35.15 |
| 09 | 6.86 | M3.22 | 4.08 | 1.30 | 0.98 | 1.05 | M0.17 | 0.69 | 1.60 | M2.01 | M6.70 | M5.23 | 35.57 |
| 10 | M5.39 | 3.65 | M6.04 | M4.16 | M3.52 | M3.72 | 0.23 | 0.17 | M2.94 | M5.77 | 7.91 | 11.43 | 54.88 |
| 11 | M5.35 | 5.17 | M8.25 | M5.58 | 3.32 | M1.48 | 1.10 | M0.00 | M1.04 | | M9.14 | M4.30 | 44.73 |
| 12 | M9.24 | M3.11 | M8.43 | 4.84 | M3.16 | M3.54 | M0.79 | M0.00 | M0.09 | M7.92 | M9.00 | M9.74 | 60.86 |
| 13 | M3.56 | 2.48 | M1.95 | | M2.69 | M0.12 | M0.00 | | M5.56 | M1.05 | M3.94 | M2.08 | 23.43 |
| 14 | M3.21 | M3.83 | M9.02 | 3.93 | M2.59 | M1.33 | 0.91 | M0.77 | 1.56 | M6.66 | M3.39 | M5.08 | 42.48 |
| 15 | M3.28 | M3.99 | 5.52 | 2.35 | M1.00 | 0.32 | 0.26 | 0.60 | 0.96 | M4.31 | M7.50 | M14.15 | 44.44 |
| 16 | M7.35 | M3.43 | M5.47 | 3.45 | 1.12 | M1.49 | M0.43 | M0.07 | | | | | 22.81 |

Product generated by ACTS NOAA Regional Climate Centers



Appendix E. Historic Aerial Imagery



Project Study Area (USACE Image, July 1936)



Project Study Area (USACE Image, May 1944)




Project Study Area (USACE Image, April 1956)



Project Study Area (USACE Image, February 1966)



Project Study Area (USACE Image, December 1977)




Project Study Area (USACE Image, June 1989)



Project Study Area June 19, 1994



Project Study Area October 3, 2002



Project Study Area July 23, 2008



Project Study Area April 17, 2015





Appendix C. Civil Design Plans



Water Quality Resource Area

Boardman Wetland Design Project

Cleckamas County Oregon

February 14, 2017



Contents

- 1 Introduction 1
- 2 Water Quality Resource Area 1
- 3 Proposed Development within the WQRA 3
 - 3.1 Sanitary Sewer Line Rehabilitation 3
 - 3.2 Wetland Enhancement 3
 - 3.3 Public Space Development 3
 - 3.4 Project Effects 4
- 4 Project Mitigation 5

Tables

- Table 1. Width of WQRA Vegetated Corridor 2
- Table 2. Summary of Project-related Impacts 5

Appendices

- Appendix A. Figures
- Appendix B. Wetland Delineation Report
- Appendix C. Civil Design Plans

Abbreviations and Acronyms

| | |
|-------|-----------------------------------|
| EPSC | Erosion Prevention Control Plan |
| HCA | Habitat Conservation Area |
| M | Medium Density |
| Metro | Portland Metropolitan region |
| OLWSD | Oak Lodge Water Services District |
| PEM | Palustrine Emergent |
| PPWF | Primary Protect Water Feature |
| R | Residential |
| UGB | urban growth boundary |
| VC | vegetated corridor |
| WQRA | Water Quality Resource Area |
| ZDO | Zoning and Development Ordinance |

1 Introduction

The application for a Water Quality Resource Area (WQRA) Development Permit has been prepared for the Oak Lodge Water Services District (OLWSD) Boardman Wetland Design Project (project) in compliance with requirements outlined in Section 709 of the Clackamas County Zoning and Development Ordinance (ZDO). The project area lies within the Portland Metropolitan region (Metro) urban growth boundary (UGB) in the northwestern portion of Clackamas County, Oregon, east of Oregon Route 99E, and north of the City of Gladstone (Figure 1, all figures are located in Appendix A). The 8.4-acre Boardman Wetlands are bordered by SE Boardman Avenue to the north, SE Cook Street to the east, SE Jennings Avenue to the south, and SE Addie Street to the west (Figure 2). The Boardman Creek drainage basin, comprised of the South and North Boardman basins, covers approximately 1,327 acres. The basin consists of 21 miles of piped creek and 4 miles of open stream. Boardman Creek enters the wetland area from a culvert beneath SE Jennings Avenue, flows approximately 1,500 feet northwest through the central portion of the wetland and exits the area via a culvert beneath SE Boardman Avenue. Boardman Creek discharges the Boardman Wetlands, flows along the Trolley Trail, through Stringfield Family Park, and enters the Willamette River at Walta Vista Street. The majority of Boardman Creek is piped beneath existing development in the area. The Boardman Wetlands and Boardman Creek are primary protected water features according to 709.02(B) and 709.02(C), respectively. These features are also mapped as primary protected water resources on the Title 3 map for Section 2e2e18 from Metro's Regional Land Information.

OLWSD is proposing improvements to wetland and utility function within the 8.4-acre Boardman Wetlands. The project would replace the sanitary sewer line and manholes, provide wetland enhancement and functional uplift for approximately half of the wetland site, and develop a public boardwalk trail system through the wetland. OLWSD has a sanitary sewer maintenance easement through the site and recently purchased approximately half of the wetland area and two adjacent residential lots on SE Addie Street. Both residential lots will be re-developed to provide parking and an outdoor classroom for use by the community and the nearby schools; however, the majority of development will occur outside of the WQRA. The proposed project activities would not result in removal of WQRA area and would not change the existing WQRA category.

2 Water Quality Resource Area

Subsection 709.06(B)(1)(a) of the Clackamas County ZDO states that a WQRA Map Verification shall be required for development that is proposed to be in the WQRA. The mapped WQRA on the Title 3 map for Township 2E, Range 2E, Section 18 shows the majority of the proposed project area is categorized as a Primary Protect Water Feature (PPWF) and as a Wetland Area (Appendix A). The WQRA mapped along Boardman Creek and the Boardman Wetlands occurs on the following taxlot parcels:

- 22E18CA02716
- 22E18CA04101
- 22E18CA04407
- 22E18CA04200
- 22E18CA04300

Per Section 709.02(E) and Table 709-1, the width of the WQRA vegetated corridor (VC) for a Primary Protected Water Resource with slopes <25% is 50 feet from the edge of bankfull stage and the delineated edge of a protected wetland (Table 1). Because the VC exhibits less than 25% canopy cover and greater than 10% surface coverage of non-native vegetation, the WQRA is considered a degraded existing vegetated corridor per Table 709-2. The corridor is dominated by residential development including impervious surfaces and landscaped lawns. In the absence of development the corridor is comprised mainly of invasive reed canary grass and Himalayan blackberry.

The Boardman Wetlands are drained by Boardman Creek which passes through the central portion of the project area and wetland. The 50-foot vegetated corridor for Boardman Creek occurs entirely within the Boardman Wetlands. A wetland delineation was performed in the project area in June 2016 by a qualified wetland specialist pursuant to the Oregon Department of State Lands wetland delineation procedures. The wetland delineation report concluded approximately 4.7 acres of Palustrine Emergent (PEM) Semipermanently Flooded wetland habitat (PEM1F) are present within the project area (Appendix B).

Table 1. Width of WQRA Vegetated Corridor

| Water Resource | Protected Water Resource Type | Slope Adjacent to Protected Water Source | Starting point from Measurements from Water Resource | Width of Vegetated Corridor |
|--------------------|-------------------------------|--|--|-----------------------------|
| Boardman Creek | Primary | <25 | Edge of bankfull stage | 50 feet |
| Delineated wetland | Primary | <25 | Delineated edge of protected wetland | 50 feet |

Boardman Creek and the majority of the Boardman Wetlands are located in an area zoned Urban Low Density Residential R-7) while the most westerly taxlots (22E18CA04200 and 22E18CA04300) are zoned Medium Density (M) Residential (MR-1). The project area is located within the Metro UGB. The overall contiguous area of vegetative cover is low structure, non-native and invasive in nature.

3 Proposed Development within the WQRA

3.1 Sanitary Sewer Line Rehabilitation

A sanitary sewer line was installed beneath Boardman Creek in 1961 and is currently managed by OLWSD. The line has reached the end of the design life and must be replaced. The line extends approximately 1500 feet through the center of the wetland and connects three lateral lines that service adjacent residences to the main trunk line. The existing sanitary sewer line through the wetland will be replaced with a new pipeline. Proposed repair to the sanitary sewer line will be completed using trenchless technology. Three existing lateral sewer lines will be restored to the main trunk line once repairs have been made. In accordance with Section 709.04(K), this action is considered maintenance, repair or improvement of utility facilities. Because portions of the WQRA would be restored and vegetation removed will be replaced with native vegetation, the proposed sanitary sewer line rehabilitation activities would be exempt from requirements of Section 709. Ingress and egress to the site will occur from the SE Addie Street lots and via the OLWSD easement located on the SE Jennings and SE Boardman Streets. The proposed action will be localized to OLWSD's sewer line easement and will not intrude further into surrounding WQRA and will not be discussed further in this application.

3.2 Wetland Enhancement

The majority of the WQRA is dominated by non-native, invasive plant species. The proposed wetland enhancement component of the project includes removing some of the invasive and non-native communities, and planting mixes of native trees and herbaceous vegetation designed to function in riparian and buffer/upland areas as well as riparian fringe and seasonally flooded areas. A series of features will be constructed throughout the wetland enhancement area for the purposes of enhancing hydrologic function. These features include hummocks and hollows, a small pond and a simulated beaver dam foundation. An existing beaver dam located on Boardman Creek in the northern portion of the project area would be removed. Although the mapped WQRA will experience temporary impacts during restoration work, the acreage of the WQRA will not be impacted and restoration activities are expected to increase the overall function of the wetland and its associated surface water features. The purpose of the proposed restoration is to enhance Boardman Wetlands and Boardman Creek, and is part of local efforts to enhance the Boardman-Rinearson Wetland Complex. Restoration work is exempt from the requirements of Section 709 as outlined in 709.04(E); therefore, these restoration activities will not be discussed further in this application.

3.3 Public Space Development

A component of the proposed project is to provide recreation and educational opportunities for the surrounding communities. The project proposes to develop a public space to provide parking and an outdoor classroom for the surrounding community and nearby Candy Lane Elementary School (see Appendix C for plan set). This development will occur on taxlots 22E18CA04200 and 22E18CA04300 located on SE Addie Street.

The majority of this development will occur outside the WQRA. The project proposes to construct an elevated boardwalk path that circumnavigates the wetland feature. Approximately 1800 feet of boardwalk would be constructed within WQRA categorized as a Primary Protected Water Resource. Due to the elevated boardwalk design and construction method, permanent impacts to the WQRA only include the area occupied by each helical screw pile. Because the boardwalk will be founded with helical screw piles, decking can be constructed from an elevated position, eliminating the need for temporary construction impacts within WQRA. The boardwalk alignment was chosen to minimize impacts to high quality wetland features. There would be up to two public ingress/egress routes to the boardwalk from taxlot 22E18CA04200 on SE Addie Street. The two pervious pavement paths connecting the boardwalk to the parking area will be 4-foot and 8-foot wide. Path construction includes excavating soils to a depth of approximately 6-8 inches, backfilling with crushed rock, and placing forms pervious pavers. Rockwalls will be installed in the WQRA to create viewing and resting opportunities for users of the public space (see Appendix C for plan set).

3.4 Project Effects

Development within the WQRA will be avoided to the extent possible; however, the project will result in temporary and permanent impacts to the WQRA. Approaches were implemented during the project design phase to minimize development impacts resulting from the footprint of boardwalk and trail system. During the design phase several alternatives were evaluated and subsequently dismissed due to the higher level of impacts. A path constructed at grade would have required substantial grading and fill within the WQRA and would have resulted in reducing water quality functions within the WQRA. A floating boardwalk design was also dismissed. This design option would have allowed the boardwalk to rest on the ground surface during periods of lower water disrupting the natural physical processes necessary for healthy plant survival and increasing the design footprint. The proposed elevated boardwalk allows those critical functions to be preserved while eliminating the need for grading and thereby minimizing the footprint of the design (Appendix C).

The project design team evaluated several path alignment alternatives through and around the wetland area using a wetland habitat map (Figure 4, Appendix A), created early during project development. This wetland habitat map highlighted areas of Oregon Ash, spirea, willow, and reed canary grass. The project team utilized this information to formulate a path alignment that would minimize impacts to the higher quality wetlands containing Oregon ash, spirea, and willow. The project also includes an extensive planting plan around the boardwalk within the WQRA. Several native plant pallets will be used to increase plant success and overall plant diversity. The diverse plants include species adapted to upland, riparian, emergent wetlands and open water environments can be found on the planting plan sheets found in Appendix C.

Although impact-reduction approaches would be incorporated, minor temporary and permanent impacts to the WQRA are anticipated during construction of the boardwalk and trail system, and during placement of rock walls (Appendix C).

Table 2. Summary of Project-related Impacts

| Construction Element | Impact Type | Location | Acreage | Square Feet |
|----------------------|-------------|----------|---------|-------------|
| Boardwalk | Permanent | PPWF | 0.007 | 284 |
| Rockwalls | Permanent | PPWF | 0.002 | 108 |
| | Temporary | PPWF | 0.019 | 836 |
| | Permanent | Corridor | 0.005 | 241 |
| | Temporary | Corridor | 0.033 | 1444 |
| Pervious Path | Permanent | PPWF | 0.008 | 344 |
| | Temporary | PPWF | 0.016 | 706 |
| | Permanent | Corridor | 0.025 | 1100 |
| | Temporary | Corridor | 0.037 | 1616 |


Overall, proposed project activities will create functional uplift in the WQRA by increasing canopy cover, reducing non-native and invasive plant species, and planting native communities that represent the vegetative composition though would naturally occur on site.

4 Project Mitigation

All temporary and permanent impacts to trees, vegetation, and soils will be mitigated on site in accordance with section 709.10 of the Clackamas County ZDO. Boardwalk design, layout, and installation technique will minimize impacts and limit disturbance to vegetation and soils in riparian and upland areas while still achieving overall project goals. Construction footprints and impacts would be minimized by developing and implementing a Construction Management Plan (Appendix C) and an Erosion Prevention and Sediment Control (EPSC) Plan (Appendix C) as outlined in 709.08. A construction work easement would be clearly marked and those areas of the WQRA not authorized for disturbance would be identified on project plans and in the field. At a minimum, the areas of the WQRA proposed to be graded for utility and restoration work will be delineated with silt fencing. All stormwater inlets will be protected for the duration of the project and will remain in place after construction activities are completed until soils on site have stabilized. The work area around the manhole within the wetland will be isolated and dewatered. Water removed from the work area will be pumped north and discharged in an area outside the WQRA. When not in use, equipment (excavators, graders, pavers, cement mixers, personnel vehicles, etc.) and material will be staged and/or stockpiled outside the WQRA on the SE Addie Street residential tax lots, 22E18CA04200 and 22E18CA04300. Project personnel and equipment ingress and egress for the site will occur mainly on the SE Addie Street lots, as well as through the OLWSD easements from SE Jennings Avenue (Figure 2). Native landscaping materials will be used and will be harvested locally where possible. Trees within the WQRA not proposed for removal during restoration work would be protected from impacts from construction equipment and native soils will be conserved onsite. Areas within the degraded WQRA that are disturbed and undisturbed by construction will be mitigated using a mix of native vegetation that would naturally occur in riparian, upland and

seasonally or permanently flooded wetlands (see planting plans, Appendix C). All debris will be removed from the project area and bare areas will be vegetated with native vegetation. Approximately 13,500 trees and herbaceous vegetation starts will be planted throughout the entire 4.7-acre wetland area as part of the proposed project. Monitoring of planting establishment will be conducted by OLWSD during until plant establishment is complete and invasive plant communities have been reduced to ensure the survivorship of newly planted native species. By implementing the mitigation and construction best management practices outlined above, the boardwalk and trail system will not impact the overall ecological function, size or value of the WQRA.


Appendix A. Figures



PROJECT LOCATION



FIGURE 1



Legend

- Project Study Area
- Water Quality Resource Area (WQRA) Vegetated Corridor
- Delineated Wetland
- Non-Delineated Wetland Boundary (est.)
- Taxlots
- Proposed Paved Trail
- Proposed Boardwalk
- Stream Location (off-site)
- Culvert
- Stream Location
- Stormwater Conveyance

DATA SOURCE: METRO 2016 HDR 2016, ESRI 2016

0 100 200 Feet






HABITAT CONSERVATION AND WATER QUALITY RESOURCE AREAS



Nature in Neighborhoods


Title 13

Section: 2s2e18

-  Section
-  Taxlot
- HCA Category**
-  High
-  Moderate
-  Low

The information on this map was derived from digital databases on which the Metro Data Resource Center has no control and cannot accept any responsibility for errors, omissions, or product accuracy. There are no warranties, expressed or implied, indicating the accuracy of the information or fitness for a particular purpose. Metro Data Resource Center reserves the right to modify any errors will be appreciated.




1 inch equals 800 feet
 Feet



METRO DATA RESOURCE CENTER

600 NORTHEAST GRAND AVENUE | PORTLAND, OREGON 97232-2736
 TEL (503) 797-1742 | FAX (503) 797-1809
 info@metrodata.or.us | www.metro-data.or.us

Figure 3. Habitat Conservation Area Map



WETLAND AND VEGETATION INVENTORY



- Legend**
- Project Study Area
 - Water Quality Resource Area (WQRA) Vegetated Corridor
 - Delineated Wetland
 - Non-Delineated Wetland Boundary (est.)
 - Taxlots
 - Proposed Paved Trail
 - Proposed Boardwalk
 - Stream Location
 - Open Water (8%), Not Mapped
 - Cedar, (A), 0.5%
 - Landscape And Wetland Species, (B), 0.8%
 - Black Cottonwood, (C), 1%
 - Spirea, (D), 1%
 - Willow, (E), 7%
 - Oregon Ash, (F), 7%
 - Himalayan Blackberry, (G), 16%
 - Reed Canary Grass, (H), 64%



DATA SOURCE: METRO 2016 HDR 2016
ESRI 2016


Appendix B. Wetland Delineation Report



Wetlands and Waterbodies Delineation Report

Boardman Wetland Design
Clackamas County, Oregon

January 9, 2017





Contents

| | | |
|-------|---|----|
| 1 | Landscape Setting and Land Use | 1 |
| 2 | Site Alterations | 2 |
| 3 | Precipitation Data and Analysis..... | 3 |
| 4 | Methods..... | 4 |
| 4.1 | Review of Existing Materials | 4 |
| 4.2 | Wetlands | 4 |
| 4.2.1 | Vegetation | 5 |
| 4.2.2 | Soils..... | 5 |
| 4.2.3 | Hydrology | 6 |
| 4.3 | Ordinary High Water Mark..... | 6 |
| 5 | Description of All Wetlands and Other Non-Wetland Waters..... | 6 |
| 5.1 | Delineated Wetlands | 6 |
| 5.2 | Waters of the State/United States..... | 8 |
| 6 | Deviation from LWI or NWI..... | 8 |
| 7 | Mapping Methods..... | 8 |
| 8 | Additional Information..... | 9 |
| 9 | Results and Conclusions..... | 9 |
| 10 | Disclaimer..... | 10 |
| 11 | References | 11 |

Tables

| | |
|--|---|
| Table 3-1. Summary of Precipitation between April and June 2016 in Oregon City, Clackamas County, Oregon | 4 |
| Table 4-1. Study Area Soils | 6 |

Appendices

- Appendix A. Figures
- Appendix B. Delineation Data Forms
- Appendix C. Ground Level Photographs
- Appendix D. WETS Table
- Appendix E. Historic Aerial Imagery

1 Landscape Setting and Land Use

Oak Lodge Sanitary District (OLSD) is proposing to improve wetland functions for approximately half of the 8.4-acre wetland known as the Boardman Wetlands, which is part of the Boardman Wetland Design project (project), (Figure 1; all figures are located in Appendix A). The project would provide rehabilitation or replacement of the sanitary sewer line and manholes in the wetland, wetland enhancement, and construction areas of the public boardwalk trail system through a portion of the wetland. OLSD has a sewer maintenance easement through the site and recently purchased approximately half of the wetland area and two adjacent residential lots on SE Addie Street: parcels 22E18CA04200 and 22E18CA04300 (Figure 2). At least one of the residential lots would be re-developed to provide parking, a public restroom, and an outdoor classroom for the nearby Candy Lane Elementary School. These lots have a direct connection to the Boardman Wetlands.

The 5.5-acre Boardman Wetland Design project study area is located within the United States Geological Survey (USGS) Gladstone Quadrangle Map (USGS 1984), Township 2 South, Range 2 East, Section 18 (Figure 1). The study area lies within the Portland Metropolitan region (Metro) urban growth boundary (UGB) in the northwestern portion of Clackamas County, Oregon, east of Oregon Route 99E, and north of the City of Gladstone. The Boardman Wetlands are bordered by SE Boardman Avenue to the north, SE Cook Street to the west, SE Jennings Avenue to the south, and SE Addie Road to the west.

As defined by the Environmental Protection Agency (EPA), the project study area occurs within the Willamette Valley Ecoregion. The Willamette Valley Ecoregion is defined by the Willamette River and consists of broad alluvial flats and low basalt hills, with soils of deep alluvial silts from river deposits and dense heavy clays from fluvial deposits. The Willamette Valley Ecoregion is relatively low gradient, and historically, the Willamette River was extensively braided. These factors contribute to the current hydrology of the valley, characterized by numerous oxbow lakes, ponds and wetlands as well as sluggish, meandering streams and rivers (EPA 2016). The project study area occurs in the EPA Level IV Ecoregion 3c, Prairie Terraces. This ecoregion supports Oregon white oak prairies, and in wetter areas supports Oregon ash and Douglas fir. This ecoregion was historically comprised of seasonal wetlands and ponds, and currently many streams are channelized, ditched, and/or diverted (EPA 2016).

The Boardman Creek drainage basin, comprised of the South and North Boardman basins, covers approximately 1,327 acres. The basin consists of 21 miles of piped creek and 4 miles of open stream. Boardman Creek begins in the Boardman Wetlands, flows along the Trolley Trail, through Stringfield Family Park, and enters the Willamette River at Walta Vista Street (NCUWC 2016). The majority of Boardman Creek is piped beneath existing development in the area. The Boardman Wetlands habitat is classified as a Palustrine Emergent (persistent) Seasonally Flooded (PEM1C) wetland by the National Wetland Inventory (NWI, Figure 3; [USFWS 2016a]).

Elevations within the Boardman Wetland Design project study area are between 67 and 75 feet above sea level. The majority of the study area is flat with slopes of less than

3 percent occurring mainly along the boundaries where the wetland area transitions to residential development. Boardman Creek enters the study area from a culvert beneath SE Jennings Avenue and travels approximately 1,500 feet from southeast to northwest forming several ponds through the central portion of the study area (Figure 5A). The creek discharges to a culvert beneath SE Boardman Avenue north of the East Side Athletic Club, located at 4606 SE Boardman Avenue (Figure 5A).

The project study area is bordered by residential development zoned R-7 (Urban Low Density Residential) occurring on SE Boardman Avenue to the north, SE Cook Street to the east, and SE Jennings Avenue to the south; development zoned MR-1 (Medium Density Residential) occurs on SE Addie Street to the west.

2 Site Alterations

Land surveys completed in the 1880s show that Boardman Creek was originally a large, unrestricted, terrace wetland with numerous small tributaries (WSM 2014). As the area began to be settled, the wetlands were extensively ditched and converted to a series of stream channels. In the early 1900s the wetlands were effectively drained for agricultural purposes (WSM 2014). The land was subsequently converted to commercial, industrial, and residential development, and was modified further by construction of the local road system and placement of utility infrastructure. Aerial imagery dating back to 1936 indicates the area may have been used for agricultural purposes (See Historic Aerial Imagery in Appendix E). The majority of SE Addie Street was developed with residences at this time but very little development had occurred on SE Jennings Avenue or SE Cook Street. No residences or businesses had been developed on SE Boardman Avenue and Boardman Creek appears to have been ditched. Agricultural uses of the wetland area apparently ceased between 1956 and 1966. Residential and infrastructure development in the area continued steadily until recently. A sanitary sewer trunk line was installed through the wetland, beneath Boardman Creek, in 1961. The majority of disturbance within the project study area over the past 15 years is associated with residential development on SE Briar Court, SE Cook Street, SE Nature Way, and SE Lucas Court (See Google Earth aerial imagery in Appendix E).

Currently the remaining wetlands are surrounded by residential development to the north, east, and west, and SE Jennings Avenue to the south. As shown in aerial imagery, the majority of the area surrounding the Boardman Wetlands had been previously developed (Appendix E). Between 2002 and 2005, four single-family dwellings were construction on SE Cook Street; parcels were also developed on SE Briar Court and SE Nature Way. In July 2007 parcels were developed on SE Lucas Court. By 2008, all development in residential areas surrounding the wetlands was completed and no other apparent site alterations have occurred since.

The historic and ongoing development of the surrounding area has degraded the overall quality of the vegetation and habitat in the study area. Previous development has significantly altered natural drainage in the area through ditching, piping, rerouting, and the installation of culverts. Areas with large amounts of impervious surface decrease infiltration and increase stormwater discharge to the wetland area. Residential development has resulted in fill material being placed along the borders of adjacent

parcels that surround the study area. Remaining, undeveloped portions of the Boardman Wetlands are vegetated; however, non-native and invasive species are abundant due to historic development and ongoing disturbance.

3 Precipitation Data and Analysis

The project study area lies within Clackamas County, which is situated at the western base of the northern Oregon Cascade Mountain Range. According to the National Climatic Data Center, the project study area is within U.S. Climate Division 2, Willamette Valley. The Oregon Climate Service describes this division as similar to a Mediterranean climate, with warm, dry summers and cool, wet winters (Taylor and Bartlett 1993). The growing season in this area lasts from February 15 to December 4 (292 days) (NRCS 2016a; Appendix D). Annual average temperatures recorded at the closest Natural Resources Conservation Service (NRCS) Climate Analysis for Wetlands (WETS) station in Oregon City (OR6334) range from 45.1°F to 64.8°F (NRCS 2016a). Average annual precipitation recorded at the WETS station is 46.05 inches (NRCS 2016a). The cooler months are the wettest, with the majority of annual rainfall occurring between November and March. Conversely, the warmer months are driest; average rainfall is less than 2 inches per month between June and September (NRCS 2016a).

Recorded precipitation data for the 3 months preceding the field survey, conducted on June 22 and June 24, 2016, were gathered from the nearest weather station in Oregon City, Oregon (Station 356334, Appendix D), and compared to the average precipitation range reported in the WETS table (Table 3-1 and Appendix D). Rainfall throughout the study area was average and normal for the month of April, below average and not within normal range during May, and below average, but within the normal range for June. Approximately 0.97 inches of rainfall was recorded during the 2 weeks prior to the field survey (June 8 - June 21, 2016). Approximately 0.52 inches of rainfall was recorded on June 22, and no rainfall was recorded on June 24. The precipitation for the water year to the date of the wetland survey (October 2015 - June 2016) is 48.62 inches; approximately 115 percent of the average water year of 42.29 inches for the same period (NRCS 2016a).

Because the current water year is above average, below average and out of normal range precipitation during the month of May is not expected to have influenced the presence or absence of vegetation, hydrologic indicators, or wetlands in the study area. Observed precipitation data in the months leading up to the field investigation was analyzed using the Direct Antecedent Rainfall Evaluation Method (NRCS 2015); climate in area was drier than normal.

Table 3-1. Summary of Precipitation between April and June 2016 in Oregon City, Clackamas County, Oregon

| Month | Recorded Precipitation (inches) | Monthly Precipitation Average (inches) | Percent of Average Recorded | 30% chance (inches) ¹ | |
|-------|---------------------------------|--|-----------------------------|----------------------------------|-----------|
| | | | | Less Than | More Than |
| April | 3.45 | 3.46 | 99.7% | <2.44 | >4.10 |
| May | 1.12 | 2.70 | 41.2% | <1.72 | >3.26 |
| June | 1.49 | 1.83 | 81.4% | <1.11 | >2.22 |

Source: NRCS 2016a (See WETS table in Appendix D)

¹ 30 percent chance less than or more than ranges for normal precipitation.

4 Methods

4.1 Review of Existing Materials

- USGS Topographical, Gladstone Quadrangle Map
- NWI, Gladstone Quadrangle Map (U.S. Fish and Wildlife Service [USFWS] 2016a) (Figure 3, Appendix A)
- Soil Survey of Clackamas County, Oregon (Gerig 1985) (Figure 4, Appendix A)
- Precipitation data from Climate Analysis for Wetlands (WETS) OR6334, Oregon City, Oregon (NRCS 2016a, Appendix F)
- Hydric Soils List, Clackamas County, Oregon (NRCS 2016b) (Figure 4, Appendix A)

4.2 Wetlands

Field investigations were conducted by HDR on June 22 and 24, 2016. The NWI identified one PEM1C wetland, which covers the majority of the study area (Figure 3, Appendix A).

The wetland area was delineated using the methods described in the United States Army Corps of Engineers' (USACE) Wetlands Delineation Manual (Environmental Laboratory 1987) and the Regional Supplement to the USACE Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region (Environmental Laboratory 2010).

Sample plots (labeled SP on figures) were taken in areas to confirm the presence and characteristics of wetland and upland areas. Plots were selected by initial observation of topographic depressions, wetland vegetation, visual evidence of hydrology, and examination of soil samples. At sites exhibiting positive indicators of wetland characteristics, multiple soil pits were dug in conjunction with analysis of vegetative and hydrologic indicators to aid in the determination of wetland boundaries. Once a plot site was selected, a soil pit was dug, soils, hydrology and vegetation were investigated, and results were recorded using the USACE Wetland Determination Data Form

(Appendix B). In many areas, the wetland continues offsite and no corresponding upland plot exists within the project study area. In areas highly modified by fill placement, the wetland boundary was determined by observed changes in vegetation communities and hydrological features similar to those observed at representative wetland sample plots in which data was collected. In these cases, test soil pits were dug to confirm the presence of wetland soils. Landscape elevations were reviewed on maps and in the field to aid in determining the wetland boundary in these areas.

Sample plot locations are shown in Figure 5A-5E in Appendix A and data forms associated with sample plots are included in Appendix B. Representative site photographs from sample plots and observation points are included in Appendix C. Methods used to determine the presence of hydric soil, hydrology, and hydrophytic vegetation are discussed below. Variations to the standard methodology, if necessary, are indicated on the data forms.

4.2.1 Vegetation

At each plot, the percent absolute cover for each species was visually estimated and recorded. Herbaceous cover was assessed within a 10-foot radius plot, and trees, shrubs, and woody vines were estimated within a 30-foot radius plot (Environmental Laboratory 1987, 2010). In accordance with USACE methodology, greater than 50 percent of the dominant plant species must be classified as hydrophytic or have a prevalence index less than or equal to 3.00 for a site to display a positive wetland vegetation indicator.

The dominant plant species were identified using standard taxonomic references (Guard 2010; Pojar and MacKinnon 2004; and Cooke 1997). The wetland indicator status for each species was determined in accordance with the National Wetland Plant List (Environmental Laboratory 2014; USACE 2016). Vegetation was recorded as obligate (OBL), facultative-wetland (FACW), facultative (FAC), facultative upland (FACU), or upland (UPL).

At the time of the wetland delineation surveys some of the herb species, including grasses and sedges, did not have additional characteristics present to help species identification. All dominant plants were identified to species level and the wetland indicator status was recorded on the datasheet. Non-dominant plants that could not be identified to the species level were omitted from the analysis. If necessary, the most common indicator status for the genus was selected to determine dominance based on the National Wetland Plant List. These instances are noted on the data sheets, where applicable.

4.2.2 Soils

Soils at each representative wetland and upland sample plot were typically inspected to a depth of 15 to 26 inches to determine the presence or absence of hydric soil indicators based on the NRCS Indicators of Hydric Soils (NRCS 2010). Soil samples were moistened when necessary to aid in the determination of soil matrix and redoximorphic features (if present): hue, value, and chroma colors (Munsell Color Services, 2009). Soil texture was evaluated using field methods described by USACE and NRCS.

Figure 4 shows the mapped soils in the study area. Table 4-1 provides soil names, hydric status, and the approximate percentage of each soil in the study area (NRCS 2016b).

Table 4-1. Study Area Soils

| Soil Type (Map Unit Symbol) | Percentage of Study Area | Hydric Status |
|---|--------------------------|-------------------------------|
| Cove silty clay loam (25) | 84.5 | Hydric |
| Woodburn silt loam, 3 to 8 percent slopes (91B) | 15.5 | Non-hydric, hydric inclusions |

Source: NRCS 2016b

Cove silty clay loam soils are deep, poorly-drained soils on floodplains formed in clayey alluvium. The surface layer of these soils is typically comprised of black silty clay loam (Gerig 1985). Woodburn silt loam soils are deep, moderately well-drained soil occurring on broad valley terraces. Surface layers are comprised of very dark brown and dark brown silt loam (Gerig 1985).

4.2.3 Hydrology

To document wetland hydrology characteristics, primary and secondary indicators were investigated at each of the sample plots. These indicators included the presence of inundation or standing water at the surface, saturation, drainage patterns, hydrogen sulfide odor, iron deposits, high water table, and/or reduced iron when using an Alpha-alpha dipyrindyl solution (alpha-alpha).

4.3 Ordinary High Water Mark

The ordinary high water mark (OHWM) for waterways in the study area was determined in the field using the methodology outlined in the USACE Regulatory Guidance Letter 05-05 (USACE 2005). The USACE guidance is consistent with the definition of OHWM put forth by the Oregon Department of State Lands (DSL). For purposes of the Clean Water Act (CWA), OHWM is “that line on the shore established by the fluctuation of water and indicated by physical characteristics such as a clear, natural line impressed on the bank, shelving, changes in the character of soil, destruction of terrestrial vegetation, the presence of litter and debris, or other appropriate means that consider the characteristics of the surrounding areas” (USACE 2005). These indicators were not observed in the field for Boardman Creek or any other water feature present on site.

5 Description of All Wetlands and Other Non-Wetland Waters

5.1 Delineated Wetlands

The Boardman Wetlands encompass approximately 8.4 total acres (Figure 5A). One wetland, Wetland A, was delineated within the 5.5-acre study area (Figure 2). Wetland A is approximately 4.7 acres and is located in a topographic depression (Figure 5A). The majority of Wetland A classifies as Palustrine Emergent Semipermanently Flooded habitat (PEM1F, [USFWS 1979]), and classifies as a Depressional wetland

hydrogeographically (Adamus 2001). A total of 15 sample plots (SP1 to SP15) were completed in the project study area. Ten sample plots were determined to be within the wetland boundary and five sample plots were determined to be within upland areas. In many areas the wetland continues outside the boundaries of the study area; in such cases, a paired upland plot was not completed due to access restrictions.

The majority of the wetland has open herbaceous cover with isolated pockets of shrubs and trees that occur mainly along the wetland borders and within the northern portion of the project study area. Herbaceous vegetation in the wetland is dominated by reed canary grass (*Phalaris arundinacea*, FACW). The tree and shrub community of the wetland is dominated by Oregon ash (*Fraxinus latifolia*, FACW) and willow species (*Salix* spp., FAC/FACW). The wetland and upland vine community, where present, is solely dominated by Himalayan blackberry (*Rubus armeniacus*, FAC). The surrounding upland community varies widely, but is mainly comprised of Oregon ash (*Fraxinus latifolia*, FACW), facultative willow species (*Salix* spp.), reed canary grass (*Phalaris arundinacea*, FACW), common velvet grass (*Holcus lanatus*), and Himalayan blackberry (*Rubus armeniacus*, FAC; See datasheets in Appendix B).

The wetland hydrology is primarily influenced by Boardman Creek and stormwater runoff from surrounding residential development that is conveyed to the wetland by several stormwater outfalls (Figure 5A-5C). Boardman Creek enters the wetland area from a culvert beneath SE Jennings Avenue, flows approximately 1,500 feet northwest through the central portion of the wetland and exits the area via a culvert beneath SE Boardman Avenue. A total of five stormwater outfalls discharge to the wetland (Figure 5A-5C). Additionally, one unmapped, open air outfall was encountered just east of the project study area (PP16, Figure 5C). Due to topographic position, field observations of highly saturated conditions, and presence of surface water throughout most of the wetland area, hydrology may also be attributed to groundwater inputs. Multiple historic aerial images evaluated over a number of years at different times of the year indicate a large portion of the study area appears to be saturated/flooded for most of the year. Historical aerial images available from the US Army Corps of Engineers and Google Earth date back to July 1936 and are shown in Appendix E. Surface saturation is visible in all images beginning in 1977; high water table is assumed throughout the wetland area for all years except years of extreme drought.

Soils within the wetland area are mapped as Cove silty clay loam (25) and Woodburn silt loam, 3 to 8 percent slopes (91B); both are hydric soils (NRCS 2016b). Soils at SP4 and SP6 were problematic due to lack of hydric soil indicators; the problematic soils procedure outlined in the Western Mountains, Valley, and Coast Regional Supplement was applied (Environmental Laboratory 2010). Problematic soil situation 4b(6), Seasonally Ponded Soils, was applied when evaluating SP4 and SP6 and soils were considered hydric. Landscape setting is likely to concentrate flow away from the sample plot in both cases.

In the northeastern portion of the study area the natural landscape has been modified by placement of fill associated with residential development on SE Briar Court. This modification has likely shifted the natural wetland boundary west and modified natural hydrology. In this area hydrology and wetland vegetation were comparable to SP10 (Figure 5C) and was used primarily to determine the wetland boundary. Additionally, test pits were dug (See Photo 34 in Appendix C for example of test pit) along the boundary

and wetland soils were confirmed by strong hydrogen sulfide odor and the presence of redoximorphic features within the upper 6 inches of soil profiles (Photo 35, Appendix C).

The wetland continues offsite along the study area boundaries to the south and southeast (Figure 5B, 5C, and 5E). Most parcels that border the wetland area to the east of the study area have been filled; therefore, the wetland is not expected to continue offsite in this area.

5.2 Waters of the State/United States

Boardman Creek enters the study area from a culvert beneath SE Jennings Avenue and travels approximately 1,500 feet from southeast to northwest forming several ponds through the central portion of the study area (Figure 5A). The creek discharges to a culvert beneath the east parking lot of the East Side Athletic Club located at 4606 SE Boardman Avenue (Figure 5A) and eventually discharges to the Willamette River at a point approximately 3,000 feet northwest of the project area, as the crow flies. Boardman Creek is an at-grade stream with an unconsolidated bottom and no defined bed and bank; therefore, no OHWM was determined during field surveys. Due to the relatively flat landscape and extensive presence of reed canary grass, the creek channel is not apparent though much of the wetland corridor. Large ponds, backwater channels and areas of standing water are prevalent through the study area. The thalweg of Boardman Creek is likely the lowest point in the area where water collects, channelizes and moves offsite. Based on these characteristics and considering the additional hydrologic inputs, Boardman Creek acts as a discharge point for the surrounding headwater wetland area. No fish species occur in Boardman Creek (Streamnet 2016).

6 Deviation from LWI or NWI

The Local Wetland Inventory (LWI) did not show any mapped wetlands within the project study area. The Boardman Wetlands are classified as a Palustrine Emergent (persistent) Seasonally Flooded (PEM1C) wetland habitat by the NWI (USFWS 2016a; Figure 4). However, based on historic aerial imagery (Appendix E) and field observations (Appendix A and Appendix C), it is likely that surface water and high water table persists throughout the year; therefore Wetland A should be classified as a Palustrine Emergent (persistent) Semipermanently flooded (PEM1F) wetland habitat.

7 Mapping Methods

During the field delineation, data plot locations, wetland boundaries, and OHWM boundaries were recorded using a resource grade Trimble GeoXH 6000 Global Positioning System (GPS). Mapping accuracy of the unit is 50 cm (1.64 feet) using post-processed differential data correction after being downloaded. Once post-processing was completed, the data were overlain onto the National Agriculture Imagery Program (NAIP) aerial photographs used for field maps with the project, and GPS data using GIS software. The data illustrated on Figure 5A-5C has a sub-meter mapping accuracy using post-processed differential data correction.

8 Additional Information

USACE and DSL will assert jurisdiction over water and wetland features that meet regulatory authority as defined by the following:

- USACE will assert jurisdiction over traditional navigable waters, which includes all the waters described in 33 C.F.R. § 328.3(a)(1), and 40 C.F.R. § 230.3 (s)(1). The agencies will assert jurisdiction over wetlands adjacent to traditional navigable waters, including over adjacent wetlands that do not have a continuous surface connection to traditional navigable waters.
- DSL regulates “waters” (including rivers and wetlands) for the State of Oregon. DSL regulates waters using volume amounts of materials (i.e., sediments) removed or filled into a regulated water resource and location of activity. Waters of the state are regulated under the Removal/Fill Law (Oregon Revised Statute [ORS] 196.795–990) are defined under OAR 141-085-0515.

Based on observations made at the site of surface or clear subsurface connections to regulated waters, including the Willamette River, and best professional judgment, Wetland A and Boardman Creek would be considered jurisdictional and regulated by both USACE and DSL:

- Wetland A meets the jurisdictional definition of a wetland by both USACE and DSL as defined in 33 C.F.R. § 328.7 and OAR 141-085-0515(4).
- Boardman Creek is connected via surface drainage to the Willamette River, which is considered jurisdictional to USACE and DSL and would be considered jurisdictional per 33 C.F.R. § 328.3(f).
- Boardman Creek within the project study area is not a fish-bearing stream and does not serve as critical habitat to any species listed under the Endangered Species Act (USFWS 2016b). No sensitive species are known to occur within the wetland (ORBIC 2016). Many wildlife species, including ducks, songbirds, red-tailed hawks, and nutria, were observed using the wetlands during field surveys.

9 Results and Conclusions

Within the project study area there is one wetland (Wetland A) and one surface water resource (Boardman Creek). Wetland A is approximately 4.7 acres, classified as a PEM1F wetland habitat located in a topographic depression that receives water from Boardman Creek, stormwater conveyance system discharges, and likely from groundwater inputs. Boardman Creek is a low-gradient, perennial, non-fish bearing stream moving through developed, residential areas in unincorporated Clackamas County to its confluence with the Willamette River. Both Wetland A and Boardman Creek would be considered jurisdictional to the USACE and DSL.

10 Disclaimer

This report documents the investigation, best professional judgment, and conclusions of the investigators. It should be considered a Preliminary Jurisdictional Determination and used at your own risk until it has been approved in writing by the DSL in accordance with OAR 141-090-0005 through 141-090-0055, and the USACE in accordance with Section 404 of the CWA (OAR 141-090-0035 [7][k]).

11 References

Adamus, P.R. 2001.

- 2001 Guidebook for Hydrogeomorphic (HGM)-based Assessment of Oregon Wetland and Riparian Sites: *Statewide Classification and Profiles*. Oregon Division of State Lands, Salem, OR, February 2001

Cooke, S. S.

- 1997 A Field Guide to the Common Wetland Plants of Western Washington and Northwestern Oregon, Seattle Audubon Society.

Environmental Laboratory

- 1987 Corps of Engineers Wetland Delineation Manual. Vicksburg, MS., U.S. Army Engineer Waterways Experiment Station, Technical Report Y-87-1.
- 2010 Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region (Version 2.0). Vicksburg, MS., U.S. Army Engineer Research and Development Center, ERDC/EL-TR-10-3. May 2010.
- 2014 State of Oregon 2014 Wetland Plant List. Lichvar, R.W., M. Butterwick, N.C. Melvin, and W.N. Kirchner. 2014. The National Wetland Plant List: 2014 Update of Wetland Ratings. Phytoneuron 2014-41: 1-42. Vicksburg, MS., U.S. Army Engineer Research and Development Center, Cold Regions Research and Engineering Laboratory, ERDC/CRREL.

Environmental Protection Agency (EPA)

- 2016 Ecoregions of the Pacific Northwest (Idaho, Oregon, Washington). U.S. EPA, National Health and Ecological Effect Research Laboratory, Western Ecology Division, Corvallis, Oregon. Map scale 1:1,500,000. Accessed September 14, 2016: <https://www.epa.gov/eco-research/ecoregion-download-files-region#pane-10>.

Gerig, Allen J.

- 1985 Soil Survey of Clackamas County Area, Oregon. United States Department of Agriculture, Soil Conservation Service. November 1985.

Guard, B. J.

- 2010 Wetland Plants of Oregon and Washington, 2nd Ed. Lone Pine Publishing.

Munsell Color

- 2009 Munsell Soil Color Charts. New York: GretagMacbeth.

National Resources Conservation Service (NRCS)

- 2010 Field Indicators of Hydric Soils in the United States: A Guide for Identifying and Delineating Hydric Soils, Version 7.0. L.M. Vasilas, G.W. Hurt, and C.V. Noble (eds.). USDA, NRCS, in cooperation with the National Technical Committee for Hydric Soils.
- 2015 Hydric Soils Technical Note 11: Hydric Soils Technical Standards and Data Submission Requirements for Field Indicators of Hydric Soils. Revised December 2015.
- 2016a USDA Field Office Climate Data – Observed Daily Data and average WETS Station Oregon City OR6334 data. Accessed September 13, 2016: <http://agacis.rcc-acis.org/41005/mtot.2016>
- 2016b Web Soil Survey. Accessed May 25, 2016: <http://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>

North Clackamas Urban Watersheds Council (NCUWC)

- 2016 Boardman Creek. Accessed September 20, 2016:
<https://ncurbanwatershed.wordpress.com/our-watersheds/boardman-creek/>

Oregon Biodiversity Information Center (ORBIC)

- 2016 Report summarizing rare, threatened and endangered plant and animal records for T2S, R2E, Sec. 18. Received June 24, 2016.

Pojar, Jim, and Andy MacKinnon (eds.)

- 2004 Plants of the Pacific Northwest Coast: Washington, Oregon, British Columbia and Alaska. Lone Pine Publishing.

StreamNet

- 2016 StreamNet Data Query for Boardman Creek. Accessed September 9, 2016:
<http://q.streamnet.org/Request.cfm?cmd=BuildPicklist&NewQuery=BuildCriteria&PicklistItem=Stream>

Taylor, George, H. and Alexi Bartlett

- 1993 The Climate of Oregon, Climate Zone 2, Willamette Valley. Oregon Climate Service, Oregon State University, Corvallis, Oregon. March, 1993.

U.S. Army Corps of Engineers (USACE)

- 2005 Regulatory Guidance Letter: Ordinary High Water Mark Identification. RGL No. 05-05. Accessed July 10, 2014: <http://www.nap.usace.army.mil/cenap-op/regulatory/rgls/rgl05-05.pdf>.
- 2016 2016 Update National Wetland Plant List. Accessed May 24, 2016:
<http://rsgisias.crrel.usace.army.mil/NWPL/>.

U.S. Fish and Wildlife Service (USFWS)

- 1979 Classification of Wetlands and Deepwater Habitats of the United States. U.S. Department of the Interior, Fish and Wildlife Service, Office of Biological Services, Washington D.C. FWS/OBS-79/31, December 1979.
- 2016a National Wetland Inventory Mapper, Oregon State. Accessed September 2016:
<https://www.fws.gov/wetlands/data/Mapper.html>.
- 2016b Critical Habitat Mapper, Oregon State. Accessed September 2016:
<http://fws.maps.arcgis.com/home/webmap/viewer.html?webmap=9d8de5e265ad4fe09893cf75b8dbfb77>.

U.S. Geological Survey (USGS)

- 1984 Topographic Map: Gladstone Quadrangle, Scale 1:24000
- 2016 National Hydrostatic Dataset Viewer. Accessed June 27, 2016:
<http://viewer.nationalmap.gov/basic/>.

Worldwater Stormwater Management (WSM)

- 2014 Ditches to streams-Benefits of recasting drainage as green infrastructure. Volume 2, Issue 1, Spring 2014. Accessed September 20, 2016:
<http://barneyandworth.com/wordpress/wp-content/uploads/2014/01/Stormwater-Management-Article.pdf>.



Appendix A. Figures


Figure 1. Project Location

Figure 2. Taxlots




Figure 3. NWI

Figure 4. NRCS Soil Survey


Figure 5. Wetland Delineation (A-E)




LEGEND

-  Project Study Area
-  PLSS Section
-  River

Miles



DATA SOURCE: METRO 2016;
ESRI 2016 HDR, 2016






**BOARDMAN WETLAND DESIGN
PROJECT LOCATION**

FIGURE 1



LEGEND

-  Project Study Area
-  Taxlot

Feet 

DATA SOURCE: METRO 2016, HDR 2016



**BOARDMAN WETLAND DESIGN
TAXLOTS**

FIGURE 2




LEGEND

-  Project Study Area
-  Wetland (NWI)
-  Taxlots



Feet



DATA SOURCE: METRO 2016. HDR 2016
NWI 2016. ESRI 2016



**BOARDMAN WETLAND DESIGN
NATIONAL WETLAND INVENTORY**

FIGURE 3



**BOARDMAN WETLAND DESIGN
MAPPED SOILS**



LEGEND

Project Study Area

Taxlots

SOILS

- Cove silty clay loam*
- Humaquepts, ponded*
- Woodburn silt loam (3 to 8 percent slopes)^
- Woodburn silt loam (8 to 15 percent slopes)^

* Hydric soils
^ Non-hydric soils (hydric inclusions)


Feet
0 100 200

DATA SOURCE: METRO 2016
NRCS 2016, HDR 2016

Legend


- Taxlots
- ▲ Upland Sample Plots
- Wetland Sample Plots
- ▶ Stream Location (off-site)
- ▬ Culvert
- Delineated Wetland:
 - Wetland A
 - Non-Delineated Wetland Boundary (est.)
 - Project Study Area
- Contour (5')
- Stream Location
- Stormwater Conveyance
- Feet
 - 0 50 100 150 200

DATA SOURCE: METRO 2016, HDR 2016, ESRI 2016



BOARDMAND WETLAND DESIGN WETLAND DELINEATION INDEX










FIGURE 5A




**BOARDMAN WETLAND DESIGN
WETLAND DELINEATION**




LEGEND

-  Project Study Area
-  Photo Direction
-  Upland Sample Plots
-  Wetland Sample Plots
-  Stream Location
-  Stormwater Conveyance
-  Delineated Wetland: Wetland A
-  Non-Delineated Wetland Boundary (est.)
-  Taxlots

Feet






DATA SOURCE: METRO 2016, HDR 2016, ESRI 2016



BOARDMAN WETLAND DESIGN
WETLAND DELINEATION

FIGURE 5C









LEGEND

-  Project Study Area
 - Stream Location
 - Upland Sample Plots
 -  Delineated Wetland: Wetland A
 - Wetland Sample Plots
 - Non-Delineated Wetland Boundary (est.)
 - Photo Direction
 - Taxlots
- Feet
- 
- DATA SOURCE: METRO 2016 HDR 2016
ESRI 2016




BOARDMAN WETLAND DESIGN
WETLAND DELINEATION

LEGEND

-  Project Study Area
-  Stream Location
-  Upland Sample Plots
-  Delineated Wetland: Wetland A
-  Wetland Sample Plots
-  Non-Delineated Wetland
-  Photo Direction
-  Wetland Boundary (est.)

Taxlots



DATA SOURCE: METRO 2016; HDR 2016; ESRI 2016



**BOARDMAN WETLAND DESIGN
WETLAND DELINEATION**

FIGURE 5E



Appendix B. Delineation Data Forms



Data Sheet Summary Index

| Associated Wetland | Plot ID | Met Vegetation Criteria | Met Soils Criteria | Met Hydrology Criteria | Is Plot within a Wetland? |
|--------------------|---------|-------------------------|--------------------|------------------------|---------------------------|
| Wetland A | SP1 | Yes | Yes | Yes | Yes |
| Wetland A | SP2 | Yes | Yes | Yes | Yes |
| Wetland A | SP3 | Yes | Yes | Yes | Yes |
| Wetland A | SP4 | Yes | Yes | Yes | Yes |
| Wetland A | SP5 | No | No | Yes | No |
| Wetland A | SP6 | Yes | Yes | Yes | Yes |
| Wetland A | SP7 | Yes | Yes | Yes | Yes |
| Wetland A | SP8 | Yes | Yes | Yes | Yes |
| Wetland A | SP9 | Yes | Yes | No | No |
| Wetland A | SP10 | Yes | Yes | Yes | Yes |
| Wetland A | SP11 | Yes | No | No | No |
| Wetland A | SP12 | Yes | No | No | No |
| Wetland A | SP13 | Yes | No | No | No |
| Wetland A | SP14 | Yes | No | No | No |
| Wetland A | SP15 | Yes | Yes | Yes | Yes |

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/22/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP1
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Floodplain Local Relief (concave, convex, none): Concave Slope(%) 1
 Subregion (LRR): A Lat: 45.392985 Long: -122.609865 Datum: NAD83

Soil Map Unit Name: Cove silty clay loam NWI Classification: PEM1C
 Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | <input checked="" type="checkbox"/> | No |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
Sunny, 58-80 deg F, no rain past 3 days.

VEGETATION— Use scientific names of plants.

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|--|-------------------------|-------------------------|-------------------------|
| <u>Tree Stratum</u> | | | |
| <u>Shrub Stratum</u> | | | |
| <u>Herb Stratum</u> (Plot size: 6 Ft) | | | |
| Phalaris arundinacea | 100 | Y | FACW |
| | 100 =Total Cover | | |
| <u>Vine Stratum</u> | | | |

Dominance Test Worksheet:

| | | |
|---|--------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 1 | (A) |
| Total Number of Dominant Species Across all Strata: | 1 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 100.0% | (A/B) |

Prevalence Index Worksheet:

| Total % Cover of: | Multiply by: | |
|--------------------------------|--------------|---------|
| OBL species | 0 x 1 = | 0 |
| FACW species | 100 x 2 = | 200 |
| FAC species | 0 x 3 = | 0 |
| FACU species | 0 x 4 = | 0 |
| UPL species | 0 x 5 = | 0 |
| Column Totals: | 100 (A) | 200 (B) |
| <i>Prevalence Index = B/A=</i> | | 2.00 |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation
 Dominance Test > 50%
 Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)
 Problematic Hydrophytic Vegetation (Explain)
 Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Plot adjacent to Boardman Creek; approx 0.5 ft west. Pedestrian mentioned observation of beaver earlier in spring when grass was shorter.

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|---------|-----|----------------|----|---|-------------------|------------|----------------------|
| | Color (moist) | | % | Color (moist) | | % | Type ¹ | | |
| 0 to 1 | 10YR | 2 / 2 | 100 | | | | | SILTY CLAY | Oi moist |
| 1 to 11 | 10YR | 2 / 2 | 20 | 2.5YR 2.5/1 | 60 | D | M | SILTY CLAY | A |
| 1 to 11 | | / | | 5YR 3/4 | 20 | C | PL | SILTY CLAY | |
| 11 to 22 | G1 | 2.5 / 1 | 100 | | | | | SILTY CLAY | B very black, gleyed |
| 22 to 24 | 5Y | 3 / 1 | 90 | 5YR 4/6 | 10 | C | PL | SILTY CLAY | Depleted |

¹Type: C=Concentration, D=Depletion, RM=Reduced Martix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? Yes No

Remarks:

Positive reaction to alpha, alpha-dipyridyl reagent. Faint depletions, very prominently black organic material (muck) filtered in horizons below.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

Surface Water Present? Yes No Depth (inches): _____
 Water Table Present? Yes No Depth (inches): 20
 Saturation Present? Yes No Depth (inches): 14
 (includes capillary fringe)

Wetland Hydrology Present? Yes No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

D2- drainage way within floodplain; D3 - potential clay layers below

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/22/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP2
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Floodplain Local Relief (concave, convex, none): None Slope(%) 0

Subregion (LRR): A Lat: 45.393633 Long: -122.611020 Datum: NAD83

Soil Map Unit Name: Cove silty clay loam NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)

Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No

Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | <input checked="" type="checkbox"/> | No |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
Sunny, 58-80 deg F, no rain past 3 days.

VEGETATION- Use scientific names of plants.

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|--|-------------------------|-------------------------|-------------------------|
| <u>Tree Stratum</u> | | | |
| <u>Shrub Stratum</u> | | | |
| <u>Herb Stratum</u> (Plot size: 6 Ft) | | | |
| Phalaris arundinacea | 80 | Y | FACW |
| Juncus effusus | 10 | N | FACW |
| Typha latifolia | 10 | N | OBL |
| Callitriche heterophylla | 3 | N | OBL |
| | 103 | =Total Cover | |

Dominance Test Worksheet:

| | | |
|---|--------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 1 | (A) |
| Total Number of Dominant Species Across all Strata: | 1 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 100.0% | (A/B) |

Prevalence Index Worksheet:

| Total % Cover of: | Multiply by: | | |
|--------------------------------|--------------|---------|---------|
| OBL species | x 1 = | 13 | |
| FACW species | x 2 = | 180 | |
| FAC species | x 3 = | 0 | |
| FACU species | x 4 = | 0 | |
| UPL species | x 5 = | 0 | |
| Column Totals: | | 103 (A) | 193 (B) |
| <i>Prevalence Index = B/A=</i> | | 1.87 | |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation

Dominance Test > 50%

Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation (Explain)

Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

| | | | |
|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No |
|--|-----|-------------------------------------|----|

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|---|----------------|---|--------|-------|------------|---------|
| | Color (moist) | % | Color (moist) | % | Type 1 | Loc 2 | | |
| 0 to 18 | / | | | | | | SILTY MUCK | Muck |

¹Type: C=Concentration, D=Depletion, RM=Reduced Martix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type:
Depth (inches):

Hydric Soil Present? Yes X No

Remarks:
Soils too saturated to determine characteristics of soil profile.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|---|----|-----------------|---|
| Surface Water Present? | Yes | X | No | Depth (inches): | 2 |
| Water Table Present? | Yes | X | No | Depth (inches): | 0 |
| Saturation Present? | Yes | X | No | Depth (inches): | 0 |

(includes capillary fringe)

Wetland Hydrology Present? Yes X No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:
D2 - Soil point adjacent to Boardman Creek. Standing water at site = 30%.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/22/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP3
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E

Landform (hillslope, terrace, etc.): Floodplain Local Relief (concave, convex, none): None Slope(%) 0
 Subregion (LRR): A Lat: 45.393930 Long: -122.612345 Datum: NAD83

Soil Map Unit Name: Woodburn silt loam, 3 to 8 percent slopes NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)

Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No

Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | <input checked="" type="checkbox"/> | No |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
Sunny, 58-80 deg F, no rain past 3 days.

VEGETATION- Use scientific names of plants.

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|--|-------------------------|-------------------------|-------------------------|
| Tree Stratum (Plot size: 30 Ft) | | | |
| Salix lasiandra | 50 | Y | FACW |
| Salix bebbiana | 20 | Y | FACW |
| Salix scouleriana | 15 | Y | FAC |
| | 85 | =Total Cover | |
| Shrub Stratum (Plot size: 30 Ft) | | | |
| Rosa woodsii | 20 | Y | FACU |
| Fraxinus latifolia | 5 | N | FACW |
| Salix bebbiana | 5 | N | FACW |
| Salix scouleriana | 5 | N | FAC |
| | 35 | =Total Cover | |
| Herb Stratum (Plot size: 6 Ft) | | | |
| Phalaris arundinacea | 60 | Y | FACW |
| Solanum dulcamara | 10 | N | FAC |
| | 70 | =Total Cover | |
| Vine Stratum | | | |

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 4 | (A) |
| Total Number of Dominant Species Across all Strata: | 5 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 80.0% | (A/B) |

Prevalence Index Worksheet:

| Total % Cover of: | | Multiply by: | |
|--------------------------------|-----|--------------|---------|
| OBL species | 0 | x 1 = | 0 |
| FACW species | 140 | x 2 = | 280 |
| FAC species | 30 | x 3 = | 90 |
| FACU species | 20 | x 4 = | 80 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 190 | (A) | 450 (B) |
| <i>Prevalence Index = B/A=</i> | | | 2.37 |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation

X Dominance Test > 50%

X Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation (Explain)

Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Hydrophytic Vegetation Present?

| | | |
|-----|-------------------------------------|----|
| Yes | <input checked="" type="checkbox"/> | No |
|-----|-------------------------------------|----|

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|-----|----------------|---|--------|-------|-----------|---------|
| | Color (moist) | | % | Color (moist) | % | Type 1 | Loc 2 | | |
| 0 to 21 | 10YR | 2 / 1 | 100 | | | | | SILT LOAM | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Martix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type:
Depth (Inches):

Hydric Soil Present? Yes **X** No

Remarks:
Positive reaction to alpha, alpha-dipyridyl reagent. Sticky soil texture.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|---|----|-----------------|---|
| Surface Water Present? | Yes | X | No | Depth (inches): | 2 |
| Water Table Present? | Yes | X | No | Depth (inches): | 0 |
| Saturation Present? | Yes | X | No | Depth (inches): | 0 |

(includes capillary fringe)

Wetland Hydrology Present? Yes **X** No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:
Standing water covered approximately 3% of total plot area. Positive reaction to alpha, alpha-dipyridyl reagent. D2 - Sample plot adjacent to Boardman Creek. D3 - Clay layers present.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County, OR Sampling Date: 6/22/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP4
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Floodplain Local Relief (concave, convex, none): None Slope(%) 0
 Subregion (LRR): A Lat: 45.394430 Long: -122.612896 Datum: NAD83
 Soil Map Unit Name: Cove silty clay loam NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | <input checked="" type="checkbox"/> | No |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
 Sunny, 58-80 deg F, no rain past 3 days. Transitional area continues south; problematic soils.

VEGETATION- Use scientific names of plants.

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|--|-------------------------|-------------------------|-------------------------|
| <u>Tree Stratum</u> (Plot size: 30 Ft) | | | |
| Corylus cornuta | 5 | Y | FACU |
| | 5 | =Total Cover | |
| <u>Shrub Stratum</u> (Plot size: 30 Ft) | | | |
| Physocarpus capitatus | 5 | Y | FACW |
| | 5 | =Total Cover | |
| <u>Herb Stratum</u> (Plot size: 6 Ft) | | | |
| Phalaris arundinacea | 80 | Y | FACW |
| Convolvulus arvensis | 2 | N | NL |
| | 82 | =Total Cover | |
| <u>Vine Stratum</u> | | | |

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 2 | (A) |
| Total Number of Dominant Species Across all Strata: | 3 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 66.7% | (A/B) |

Prevalence Index Worksheet:

| Total % Cover of: | Multiply by: | | |
|--------------------------------|--------------|-------|---------|
| OBL species | 0 | x 1 = | 0 |
| FACW species | 85 | x 2 = | 170 |
| FAC species | 0 | x 3 = | 0 |
| FACU species | 5 | x 4 = | 20 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 90 | (A) | 190 (B) |
| <i>Prevalence Index = B/A=</i> | | | 2.11 |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation

X Dominance Test > 50%

X Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation (Explain)

Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

| | | | |
|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No |
|--|-----|-------------------------------------|----|

% Bare Ground in Herb Stratum 0
 Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|----------------|-----|-------------------|------------------|-----------------|-------------------------|
| | Color (moist) | % | Color (moist) | % | Type ¹ | Loc ² | | |
| to | / | | 7.5YR 4/3 | 1 | D | M | SILTY CLAY LOAM | Grey depleted inclusion |
| to | / | | 2.5YR 8/4 | 1 | C | M | SILTY CLAY LOAM | Dark when wet |
| 0 to 1 | / | | | | | | | Oa layer, dry duff |
| 1 to 13 | 10YR | 2 / 1 | | 100 | | | SILTY CLAY LOAM | A |
| 13 to 21 | 10YR | 2 / 1 | 2.5YR 8/4 | 1 | C | PL | SILTY CLAY LOAM | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains, ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? Yes X No

Remarks:
Dark organic material translocated to layers below surface. Soils considered problematic due to lack of indicators; problematic hydric soil procedure applied. Hydrophytic vegetation, saturation and high water table is present. Landscape setting is likely to concentrate water at gentle toe of slope just east of sample plot along transitional area of wetland boundary. Area may be seasonally ponded, 4b(6) p.113, organic matter might mask features in upper 12 inches of soil. Due to presence of wetland vegetation and hydrology, soils considered hydric.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag. (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

Surface Water Present? Yes No X Depth (inches): _____
Water Table Present? Yes X No Depth (inches): 12
Saturation Present? Yes X No Depth (inches): 11
(includes capillary fringe)

Wetland Hydrology Present? Yes X No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

D2 - Sample plot adjacent to floodplain.

Remarks:

D2 - Sample plot adjacent to floodplain.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/22/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP5
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Elevation (hillslope, terrace, etc.): Terrace Local Relief (concave, convex, none): Concave Slope(%) 2-3
 Subregion (LRR): A Lat: 45.394815 Long: -122.613636 Datum: NAD83

Soil Map Unit Name: Woodburn silt loam, 3 to 8 percent slopes NWI Classification: PEM1C
 Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology, significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology, naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|-------------------------------------|--|-----|----|-------------------------------------|
| Hydrophytic Vegetation Present? | Yes | No | <input checked="" type="checkbox"/> | Is the Sampled Area within a Wetland? | Yes | No | <input checked="" type="checkbox"/> |
| Hydric Soil Present? | Yes | No | <input checked="" type="checkbox"/> | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
 Sunny, 58-80 deg F, no rain past 3 days.

VEGETATION— Use scientific names of plants.

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|---|-------------------------|-------------------------|-------------------------|
| <u>Tree Stratum</u> | | | |
| <u>Shrub Stratum</u> (Plot size: <u>30 Ft</u>) | | | |
| Crataegus monogyna | 3 | Y | FAC |
| | 3 | =Total Cover | |
| <u>Herb Stratum</u> (Plot size: <u>6 Ft</u>) | | | |
| Lapsana communis | 15 | Y | FACU |
| Hedera helix | 7 | Y | FACU |
| Phalaris arundinacea | 3 | N | FACW |
| Bromus tectorum | 2 | N | NL |
| Convolvulus arvensis | 2 | N | NL |
| | 29 | =Total Cover | |
| <u>Vine Stratum</u> (Plot size: <u>30 Ft</u>) | | | |
| Rubus armeniacus | 75 | Y | FACU |
| | 75 | =Total Cover | |

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 1 | (A) |
| Total Number of Dominant Species Across all Strata: | 4 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 25.0% | (A/B) |

Prevalence Index Worksheet:

| Total % Cover of: | Multiply by: | |
|--------------------------------|----------------|----------------|
| OBL species | 0 x 1 = | 0 |
| FACW species | 3 x 2 = | 6 |
| FAC species | 3 x 3 = | 9 |
| FACU species | 97 x 4 = | 388 |
| UPL species | 0 x 5 = | 0 |
| Column Totals: | 103 (A) | 403 (B) |
| <i>Prevalence Index = B/A=</i> | | 3.91 |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation

Dominance Test > 50%

Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation (Explain)

Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

West side of plot reduced due to position along fence and parking lot.

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|----------------|---|--------|-------|-----------|---------------------------------|
| | Color (moist) | % | Color (moist) | % | Type 1 | Loc 2 | | |
| 0 to 18 | 10YR | 2 / 1 | 100 | | | | CLAY LOAM | Soil uniform throughout sample. |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol (A1) | <input type="checkbox"/> Sandy Redox (S5) |
| <input type="checkbox"/> Histic Epipedon (A2) | <input type="checkbox"/> Stripped Matrix (S6) |
| <input type="checkbox"/> Black Histic (A3) | <input type="checkbox"/> Loamy Mucky Mineral (F1) (except MLRA 1) |
| <input type="checkbox"/> Hydrogen Sulfide (A4) | <input type="checkbox"/> Loamy Gleyed Matrix (F2) |
| <input type="checkbox"/> Depleted Below Dark Surface (A11) | <input type="checkbox"/> Depleted Matrix (F3) |
| <input type="checkbox"/> Thick Dark Surface (A12) | <input type="checkbox"/> Redox Dark Surface (F6) |
| <input type="checkbox"/> Sandy Mucky Mineral (S1) | <input type="checkbox"/> Depleted Dark Surface (F7) |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4) | <input type="checkbox"/> Redox Depressions (F8) |

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? Yes No **X**

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- | | |
|--|--|
| <input type="checkbox"/> Surface Water (A1) | <input type="checkbox"/> Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B) |
| <input type="checkbox"/> High Water Table (A2) | <input type="checkbox"/> Salt Crust (B11) |
| <input type="checkbox"/> Saturation (A3) | <input type="checkbox"/> Aquatic Invertebrates (B13) |
| <input type="checkbox"/> Water Marks (B1) | <input type="checkbox"/> Hydrogen Sulfide Odor (C1) |
| <input type="checkbox"/> Sediment Deposits (B2) | <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) |
| <input type="checkbox"/> Drift Deposits (B3) | <input type="checkbox"/> Presence of Reduced Iron (C4) |
| <input type="checkbox"/> Algal Mat or Crust (B4) | <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) |
| <input type="checkbox"/> Iron Deposits (B5) | <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) |
| <input type="checkbox"/> Surface Soil Cracks (B6) | <input type="checkbox"/> Other (Explain in Remarks) |
| <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) | |
| <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8) | |

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag. (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|----|----|-----------------|----|
| Surface Water Present? | Yes | No | X | Depth (inches): | |
| Water Table Present? | Yes | X | No | Depth (inches): | 20 |
| Saturation Present? | Yes | X | No | Depth (inches): | 14 |

(includes capillary fringe)

Wetland Hydrology Present? Yes X No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

D2 - Adjacent to floodplain.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County, Oregon Sampling Date: 6/22/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP6
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Depression Local Relief (concave, convex, none): Concave Slope(%) 0

Subregion (LRR): A Lat: 45.394824 Long: -122.613623 Datum: NAD83

Soil Map Unit Name: Woodburn silt loam, 3 to 8 percent slopes NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)

Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No

Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | |
|---------------------------------|-----|-------------------------------------|----|--|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | Yes <input checked="" type="checkbox"/> No |

Remarks: Sunny, 58-80 deg F, no rain past 3 days. Transitional area, soil pit was dug ~4-5 feet east of SP5; 6 feet east of SP5 is flooded.

| VEGETATION— Use scientific names of plants. | Absolute % Cover | Dominant Species | Indicator Status | Dominance Test Worksheet: | |
|---|------------------|------------------|------------------|---|-----------------|
| <u>Tree Stratum</u> (Plot size: 30 Ft) | | | | Number of Dominant Species That Are OBL, FACW, or FAC: | 5 (A) |
| Fraxinus latifolia | 20 | Y | FACW | Total Number of Dominant Species Across all Strata: | 6 (B) |
| | 20 | =Total Cover | | | |
| <u>Shrub Stratum</u> (Plot size: 30 Ft) | | | | Percent of Dominant Species That Are OBL, FACW, or FAC: | 83.3% (A/B) |
| Physocarpus capitatus | 30 | Y | FACW | | |
| Spiraea douglasii | 30 | Y | FACW | Prevalence Index Worksheet: | |
| Crataegus monogyna | 20 | Y | FAC | | |
| | 80 | =Total Cover | | Total % Cover of: | Multiply by: |
| <u>Herb Stratum</u> (Plot size: 6 Ft) | | | | OBL species | 0 x 1 = 0 |
| Phalaris arundinacea | 65 | Y | FACW | FACW species | 147 x 2 = 294 |
| Convolvulus arvensis | 3 | N | NL | FAC species | 20 x 3 = 60 |
| Juncus effusus | 2 | N | FACW | FACU species | 15 x 4 = 60 |
| | 70 | =Total Cover | | UPL species | 0 x 5 = 0 |
| <u>Vine Stratum</u> (Plot size: 30 Ft) | | | | Column Totals: | 182 (A) 414 (B) |
| Rubus armeniacus | 15 | Y | FACU | <i>Prevalence Index = B/A = 2.27</i> | |
| | 15 | =Total Cover | | Hydrophytic Vegetation Indicators: | |
| | | | | Rapid Test for Hydrophytic Vegetation | |
| | | | | X Dominance Test > 50% | |
| | | | | X Prevalence Index ≤ 3.0 | |
| | | | | Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet) | |
| | | | | Problematic Hydrophytic Vegetation (Explain) | |
| | | | | Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic. | |
| | | | | Hydrophytic Vegetation Present? Yes <input checked="" type="checkbox"/> No | |

% Bare Ground in Herb Stratum 5
 Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

| Depth (inches) | Matrix | | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|-----|----------------|---|---|-------------------|-----------|---------|
| | Color (moist) | | % | Color (moist) | | % | Type ¹ | | |
| 1 to 16 | 10YR | 2 / 1 | 100 | | | | | SILT LOAM | |
| 16 to 18 | 10YR | 2 / 1 | 99 | 10YR 4/1 | 1 | D | M | SILT LOAM | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Martix, CS=Covered or Coated Sand Grains.

²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol (A1) | <input type="checkbox"/> Sandy Redox (S5) |
| <input type="checkbox"/> Histic Epipedon (A2) | <input type="checkbox"/> Stripped Matrix (S6) |
| <input type="checkbox"/> Black Histic (A3) | <input type="checkbox"/> Loamy Mucky Mineral (F1) (except MLRA 1) |
| <input type="checkbox"/> Hydrogen Sulfide (A4) | <input type="checkbox"/> Loamy Gleyed Matrix (F2) |
| <input type="checkbox"/> Depleted Below Dark Surface (A11) | <input type="checkbox"/> Depleted Matrix (F3) |
| <input type="checkbox"/> Thick Dark Surface (A12) | <input type="checkbox"/> Redox Dark Surface (F6) |
| <input type="checkbox"/> Sandy Mucky Mineral (S1) | <input type="checkbox"/> Depleted Dark Surface (F7) |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4) | <input type="checkbox"/> Redox Depressions (F8) |

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? Yes **X** No

Remarks: Positive reaction to alpha, alpha-dipyridyl reagent within upper 3 inches of soil sample. No hydric soils indicators present; problematic hydric soil procedure applied due to presence hydrophytic vegetation and wetland hydrology on site. Due to landscape position on wetland transitional area, water is likely to concentrate farther east.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- | | |
|--|--|
| <input checked="" type="checkbox"/> Surface Water (A1) | <input type="checkbox"/> Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B) |
| <input checked="" type="checkbox"/> High Water Table (A2) | <input type="checkbox"/> Salt Crust (B11) |
| <input checked="" type="checkbox"/> Saturation (A3) | <input type="checkbox"/> Aquatic Invertebrates (B13) |
| <input type="checkbox"/> Water Marks (B1) | <input type="checkbox"/> Hydrogen Sulfide Odor (C1) |
| <input type="checkbox"/> Sediment Deposits (B2) | <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) |
| <input type="checkbox"/> Drift Deposits (B3) | <input checked="" type="checkbox"/> Presence of Reduced Iron (C4) |
| <input type="checkbox"/> Algal Mat or Crust (B4) | <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) |
| <input type="checkbox"/> Iron Deposits (B5) | <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) |
| <input type="checkbox"/> Surface Soil Cracks (B6) | <input type="checkbox"/> Other (Explain in Remarks) |
| <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) | |
| <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8) | |

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag. (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|---|----|-----------------|---|
| Surface Water Present? | Yes | X | No | Depth (inches): | 2 |
| Water Table Present? | Yes | X | No | Depth (inches): | 9 |
| Saturation Present? | Yes | X | No | Depth (inches): | 2 |

(includes capillary fringe)

Wetland Hydrology Present? Yes **X** No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

Positive reaction to alpha, alpha-dipyridyl reagent. D2 - Adjacent to floodplain.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/22/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP7
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Depression Local Relief (concave, convex, none): Concave Slope(%) 0

Subregion (LRR): A Lat: 45.394832 Long: -122.61361 Datum: NAD83

Soil Map Unit Name: Woodburn silt loam, 3 to 8 percent slopes NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)

Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No

Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | <input checked="" type="checkbox"/> | No |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
Sunny, 58-80 deg F, no rain past 3 days.

VEGETATION— Use scientific names of plants.

Tree Stratum (Plot size: 30 Ft)

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|--------------------|-------------------------|-------------------------|-------------------------|
| Fraxinus latifolia | 20 | Y | FACW |
| | 20 | =Total Cover | |

Shrub Stratum (Plot size: 30 Ft)

| | | | |
|-----------------------|----|--------------|------|
| Physocarpus capitatus | 30 | Y | FACW |
| Spiraea douglasii | 30 | Y | FACW |
| Crataegus monogyna | 20 | Y | FAC |
| | 80 | =Total Cover | |

Herb Stratum (Plot size: 6 Ft)

| | | | |
|----------------------|----|--------------|------|
| Phalaris arundinacea | 65 | Y | FACW |
| Convolvulus arvensis | 3 | N | NL |
| Juncus effusus | 2 | N | FACW |
| | 70 | =Total Cover | |

Vine Stratum (Plot size: 30 Ft)

| | | | |
|------------------|----|--------------|------|
| Rubus armeniacus | 15 | Y | FACU |
| | 15 | =Total Cover | |

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 5 | (A) |
| Total Number of Dominant Species Across all Strata: | 6 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 83.3% | (A/B) |

Prevalence Index Worksheet:

| | Total % Cover of: | Multiply by: | |
|--------------------------------|-------------------|--------------|---------|
| OBL species | 0 | x 1 = | 0 |
| FACW species | 147 | x 2 = | 294 |
| FAC species | 20 | x 3 = | 60 |
| FACU species | 15 | x 4 = | 60 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 182 | (A) | 414 (B) |
| <i>Prevalence Index = B/A=</i> | | 2.27 | |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation

X Dominance Test > 50%

X Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation (Explain)

Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Hydrophytic Vegetation Present? Yes No

% Bare Ground in Herb Stratum 5

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|----------------|---|-------------------|------------------|-----------|---------|
| | Color (moist) | % | Color (moist) | % | Type ¹ | Loc ² | | |
| 0 to 15 | 10YR | 3 / 2 | 100 | | | | SILT LOAM | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type:
Depth (inches):

Hydric Soil Present? Yes X No

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|---|----|-----------------|---|
| Surface Water Present? | Yes | X | No | Depth (inches): | 6 |
| Water Table Present? | Yes | X | No | Depth (inches): | 0 |
| Saturation Present? | Yes | X | No | Depth (inches): | 0 |

(includes capillary fringe)

Wetland Hydrology Present? Yes X No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

D2 - Adjacent to floodplain.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP8
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Floodplain Local Relief (concave, convex, none): Concave Slope(%) 0
 Subregion (LRR): A Lat: 45.394198 Long: -122.611585 Datum: NAD83
 Soil Map Unit Name: Cove silty clay loam NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | <input checked="" type="checkbox"/> | No |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

VEGETATION— Use scientific names of plants.

Tree Stratum

Shrub Stratum (Plot size: 30 Ft)

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|--------------------|-------------------------|-------------------------|-------------------------|
| Rosa woodsii | 60 | Y | FACU |
| Spiraea douglasii | 30 | Y | FACW |
| Crataegus monogyna | 25 | Y | FAC |
| | 115 | =Total Cover | |

Herb Stratum (Plot size: 6 Ft)

| | | | |
|----------------------|---|--------------|------|
| Phalaris arundinacea | 5 | Y | FACW |
| | 5 | =Total Cover | |

Vine Stratum (Plot size: 30 Ft)

| | | | |
|------------------|---|--------------|------|
| Rubus armeniacus | 7 | Y | FACU |
| | 7 | =Total Cover | |

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 3 | (A) |
| Total Number of Dominant Species Across all Strata: | 5 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 60.0% | (A/B) |

Prevalence Index Worksheet:

| | Total % Cover of: | Multiply by: | |
|--------------------------------|-------------------|--------------|---------|
| OBL species | 0 | x 1 = | 0 |
| FACW species | 35 | x 2 = | 70 |
| FAC species | 25 | x 3 = | 75 |
| FACU species | 67 | x 4 = | 268 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 127 | (A) | 413 (B) |
| <i>Prevalence Index = B/A=</i> | | | 3.25 |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation
 X Dominance Test > 50%
 Prevalence Index ≤ 3.0
 Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)
 Problematic Hydrophytic Vegetation (Explain)
 Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

| | | | |
|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No |
|--|-----|-------------------------------------|----|

% Bare Ground in Herb Stratum <1

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|----------------|-----------|-------------------|------------------|---------|---------------------------|
| | Color (moist) | % | Color (moist) | % | Type ¹ | Loc ² | | |
| 0 to 13 | 10YR | 2 / 1 | 100 | | | | LOAM | A - Loam, black and mucky |
| 13 to 15 | 10YR | 2 / 1 | 95 | 7.5YR 3/4 | 5 | C | M | LOAM |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? Yes **X** No

Remarks:
Positive reaction to alpha, alpha-dipyridyl reagent. Soils saturated.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag. (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|----|----|-----------------|---|
| Surface Water Present? | Yes | No | X | Depth (inches): | |
| Water Table Present? | Yes | X | No | Depth (inches): | 7 |
| Saturation Present? | Yes | X | No | Depth (inches): | 0 |

(includes capillary fringe)

Wetland Hydrology Present? Yes **X** No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:
Positive reaction to alpha, alpha-dipyridyl reagent. D2 - Adjacent to floodplain.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP9
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Surface Form (hillslope, terrace, etc.): Terrace Local Relief (concave, convex, none): None Slope(%) 2% to w
 Subregion (LRR): A Lat: 45.394624 Long: -122.611928 Datum: NAD83
 Soil Map Unit Name: Cove silty clay loam NWI Classification: None

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|-------------------------------------|--|-----|----|-------------------------------------|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | No | <input checked="" type="checkbox"/> |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | No | <input checked="" type="checkbox"/> | | | | |

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

| VEGETATION— Use scientific names of plants. | Absolute % Cover | Dominant Species | Indicator Status | Dominance Test Worksheet: | | | |
|---|------------------|------------------|------------------|---|-------------------------------------|--------------|---------|
| <u>Tree Stratum</u> (Plot size: 30 Ft) | | | | Number of Dominant Species That Are OBL, FACW, or FAC: | 2 | (A) | |
| Fraxinus latifolia | 75 | Y | FACW | Total Number of Dominant Species Across all Strata: | 3 | (B) | |
| | 75 =Total Cover | | | Percent of Dominant Species That Are OBL, FACW, or FAC: | 66.7% | (A/B) | |
| <u>Shrub Stratum</u> | | | | Prevalence Index Worksheet: | | | |
| <u>Herb Stratum</u> (Plot size: 6 Ft) | | | | Total % Cover of: | | Multiply by: | |
| Phalaris arundinacea | 10 | Y | FACW | OBL species | 0 | x 1 = | 0 |
| Equisetum arvense | 3 | N | FAC | FACW species | 85 | x 2 = | 170 |
| | 13 =Total Cover | | | FAC species | 3 | x 3 = | 9 |
| <u>Vine Stratum</u> (Plot size: 30 Ft) | | | | FACU species | 80 | x 4 = | 320 |
| Rubus armeniacus | 80 | Y | FACU | UPL species | 0 | x 5 = | 0 |
| | 80 =Total Cover | | | Column Totals: | 168 | (A) | 499 (B) |
| | | | | <i>Prevalence Index = B/A= 2.97</i> | | | |
| | | | | Hydrophytic Vegetation Indicators: | | | |
| | | | | Rapid Test for Hydrophytic Vegetation | | | |
| | | | | X Dominance Test > 50% | | | |
| | | | | X Prevalence Index ≤ 3.0 | | | |
| | | | | Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet) | | | |
| | | | | Problematic Hydrophytic Vegetation (Explain) | | | |
| | | | | Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic. | | | |
| | | | | Hydrophytic Vegetation Present? | | | |
| | | | | Yes | <input checked="" type="checkbox"/> | No | |

% Bare Ground in Herb Stratum 0
 Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-----|----------------|----|-------------------|------------------|-----------|-----------------|
| | Color (moist) | % | Color (moist) | % | Type ¹ | Loc ² | | |
| to | / | | 5YR 4/8 | 30 | C | M | CLAY LOAM | |
| 0 to 10 | 10YR 2 / 2 | 100 | | | | | CLAY LOAM | Ai - Many roots |
| 10 to 16 | 10YR 2 / 1 | 10 | 10YR 4/1 | 60 | D | M | CLAY LOAM | Bw - Compacted |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type:
Depth (inches):

Hydric Soil Present? Yes X No

Remarks:
Shovel refusal at 16" due to soil compaction and presence of root systems.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag. (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

Surface Water Present? Yes No X Depth (inches):
 Water Table Present? Yes No X Depth (inches):
 Saturation Present? Yes No X Depth (inches):
 (includes capillary fringe)

Wetland Hydrology Present? Yes No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:
No apparent signs of moisture or saturation to depth of 16"; assumed no dry season water table present. Sample plot elevation 2 feet higher than floodplain. Possible transition area

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP10
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Floodplain Local Relief (concave, convex, none): Concave Slope(%) 1% to w
 Subregion (LRR): A Lat: 45.395042 Long: -122.612813 Datum: NAD83

Soil Map Unit Name: Cove silty clay loam NWI Classification: PEM1C
 Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology, significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology, naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | Yes | <input checked="" type="checkbox"/> | No |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

VEGETATION- Use scientific names of plants.

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|---|-------------------------|-------------------------|-------------------------|
| Tree Stratum (Plot size: 30 Ft) | | | |
| Fraxinus latifolia | 40 | Y | FACW |
| | 40 =Total Cover | | |
| Shrub Stratum | | | |
| Herb Stratum (Plot size: 6 Ft) | | | |
| Phalaris arundinacea | 80 | Y | FACW |
| Equisetum arvense | 3 | N | FAC |
| | 83 =Total Cover | | |
| Vine Stratum (Plot size: 30 Ft) | | | |
| Rubus armeniacus | 20 | Y | FACU |
| | 20 =Total Cover | | |

| | | | |
|---|-------|--------------|---------|
| Dominance Test Worksheet: | | | |
| Number of Dominant Species That Are OBL, FACW, or FAC: | 2 | (A) | |
| Total Number of Dominant Species Across all Strata: | 3 | (B) | |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 66.7% | (A/B) | |
| Prevalence Index Worksheet: | | | |
| Total % Cover of: | | Multiply by: | |
| OBL species | 0 | x 1 = | 0 |
| FACW species | 120 | x 2 = | 240 |
| FAC species | 3 | x 3 = | 9 |
| FACU species | 20 | x 4 = | 80 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 143 | (A) | 329 (B) |
| <i>Prevalence Index = B/A=</i> | | 2.30 | |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation

X Dominance Test > 50%

X Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation (Explain)

Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

| | | | |
|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No |
|--|-----|-------------------------------------|----|

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|-----|----------------|---|---|-------------------|-----------|-------------------|
| | Color (moist) | | % | Color (moist) | | % | Type ¹ | | |
| 0 to 7 | 10YR | 2 / 1 | 100 | | | | | CLAY LOAM | Very black matrix |
| 7 to 16 | 10YR | 2 / 1 | 93 | 7.5YR 3/3 | 7 | C | M | CLAY LOAM | Very black matrix |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol (A1) | <input type="checkbox"/> Sandy Redox (S5) |
| <input type="checkbox"/> Histic Epipedon (A2) | <input type="checkbox"/> Stripped Matrix (S6) |
| <input type="checkbox"/> Black Histic (A3) | <input type="checkbox"/> Loamy Mucky Mineral (F1) (except MLRA 1) |
| <input checked="" type="checkbox"/> Hydrogen Sulfide (A4) | <input type="checkbox"/> Loamy Gleyed Matrix (F2) |
| <input type="checkbox"/> Depleted Below Dark Surface (A11) | <input type="checkbox"/> Depleted Matrix (F3) |
| <input type="checkbox"/> Thick Dark Surface (A12) | <input type="checkbox"/> Redox Dark Surface (F6) |
| <input type="checkbox"/> Sandy Mucky Mineral (S1) | <input type="checkbox"/> Depleted Dark Surface (F7) |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4) | <input type="checkbox"/> Redox Depressions (F8) |

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? Yes X No

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- | | |
|--|--|
| <input type="checkbox"/> Surface Water (A1) | <input type="checkbox"/> Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B) |
| <input type="checkbox"/> High Water Table (A2) | <input type="checkbox"/> Salt Crust (B11) |
| <input checked="" type="checkbox"/> Saturation (A3) | <input type="checkbox"/> Aquatic Invertebrates (B13) |
| <input type="checkbox"/> Water Marks (B1) | <input type="checkbox"/> Hydrogen Sulfide Odor (C1) |
| <input type="checkbox"/> Sediment Deposits (B2) | <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) |
| <input type="checkbox"/> Drift Deposits (B3) | <input type="checkbox"/> Presence of Reduced Iron (C4) |
| <input type="checkbox"/> Algal Mat or Crust (B4) | <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) |
| <input type="checkbox"/> Iron Deposits (B5) | <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) |
| <input type="checkbox"/> Surface Soil Cracks (B6) | <input type="checkbox"/> Other (Explain in Remarks) |
| <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) | |
| <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8) | |

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|----|----|-----------------|----|
| Surface Water Present? | Yes | No | X | Depth (inches): | |
| Water Table Present? | Yes | X | No | Depth (inches): | 16 |
| Saturation Present? | Yes | X | No | Depth (inches): | 10 |

(includes capillary fringe)

Wetland Hydrology Present? Yes X No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

D2 - Within floodplain

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County, OR Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP11
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Terrace Local Relief (concave, convex, none): None Slope(%) 2% to w
 Subregion (LRR): A Lat: 45.395042 Long: -122.612813 Datum: NAD83
 Soil Map Unit Name: Cove silty clay loam NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | |
|---------------------------------|-----|-------------------------------------|----|-------------------------------------|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | |
| Hydric Soil Present? | Yes | | No | <input checked="" type="checkbox"/> |
| Wetland Hydrology Present? | Yes | | No | <input checked="" type="checkbox"/> |

Is the Sampled Area within a Wetland? Yes No

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

VEGETATION— Use scientific names of plants.

Tree Stratum (Plot size: 30 Ft)

| | | | |
|-------------------|----|--------------|-----|
| Salix X pendulina | 40 | Y | FAC |
| | 40 | =Total Cover | |

Shrub Stratum

Herb Stratum (Plot size: 6 Ft)

| | | | |
|------------------------|----|--------------|------|
| Phalaris arundinacea | 65 | Y | FACW |
| Impatiens noli-tangere | 7 | Y | FACW |
| Equisetum arvense | 3 | N | FAC |
| Galium aparine | 3 | N | FACU |
| Rumex conglomeratus | 3 | N | FACW |
| Solanum dulcamara | 3 | N | FAC |
| | 84 | =Total Cover | |

Vine Stratum (Plot size: 30 Ft)

| | | | |
|------------------|----|--------------|------|
| Rubus armeniacus | 50 | Y | FACU |
| | 50 | =Total Cover | |

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 3 | (A) |
| Total Number of Dominant Species Across all Strata: | 4 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 75.0% | (A/B) |

Prevalence Index Worksheet:

| | | | |
|--------------------------------|-----|--------------|---------|
| Total % Cover of: | | Multiply by: | |
| OBL species | 0 | x 1 = | 0 |
| FACW species | 75 | x 2 = | 150 |
| FAC species | 46 | x 3 = | 138 |
| FACU species | 53 | x 4 = | 212 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 174 | (A) | 500 (B) |
| <i>Prevalence Index = B/A=</i> | | 2.87 | |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation

X Dominance Test > 50%

X Prevalence Index ≤ 3.0

Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation (Explain)

Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Hydrophytic Vegetation Present? Yes No

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|-----|----------------|----|---|-------------------|-----------|------------|
| | Color (moist) | | % | Color (moist) | | % | Type ¹ | | |
| 0 to 13 | 10YR | 2 / 1 | 100 | | | | | LOAM | Soils dark |
| 13 to 18 | 10YR | 2 / 1 | 90 | 5YR 4/6 | 10 | C | M,PL | CLAY LOAM | |
| 18 to 26 | 10YR | 2 / 1 | 65 | 10YR 3/6 | 15 | C | M | CLAY LOAM | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol (A1) | <input type="checkbox"/> Sandy Redox (S5) |
| <input type="checkbox"/> Histic Epipedon (A2) | <input type="checkbox"/> Stripped Matrix (S6) |
| <input type="checkbox"/> Black Histic (A3) | <input type="checkbox"/> Loamy Mucky Mineral (F1) (except MLRA 1) |
| <input type="checkbox"/> Hydrogen Sulfide (A4) | <input type="checkbox"/> Loamy Gleyed Matrix (F2) |
| <input type="checkbox"/> Depleted Below Dark Surface (A11) | <input type="checkbox"/> Depleted Matrix (F3) |
| <input type="checkbox"/> Thick Dark Surface (A12) | <input type="checkbox"/> Redox Dark Surface (F6) |
| <input type="checkbox"/> Sandy Mucky Mineral (S1) | <input type="checkbox"/> Depleted Dark Surface (F7) |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4) | <input type="checkbox"/> Redox Depressions (F8) |

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type:
Depth (inches):

Hydric Soil Present? Yes No X

Remarks:
Negative reaction to alpha, alpha-dipyridyl reagent. Features may be masked by organic material. Pockets of moisture at 10" but not consistently saturated.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- | | |
|--|--|
| <input type="checkbox"/> Surface Water (A1) | <input type="checkbox"/> Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B) |
| <input type="checkbox"/> High Water Table (A2) | <input type="checkbox"/> Salt Crust (B11) |
| <input type="checkbox"/> Saturation (A3) | <input type="checkbox"/> Aquatic Invertebrates (B13) |
| <input type="checkbox"/> Water Marks (B1) | <input type="checkbox"/> Hydrogen Sulfide Odor (C1) |
| <input type="checkbox"/> Sediment Deposits (B2) | <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) |
| <input type="checkbox"/> Drift Deposits (B3) | <input type="checkbox"/> Presence of Reduced Iron (C4) |
| <input type="checkbox"/> Algal Mat or Crust (B4) | <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) |
| <input type="checkbox"/> Iron Deposits (B5) | <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) |
| <input type="checkbox"/> Surface Soil Cracks (B6) | <input type="checkbox"/> Other (Explain in Remarks) |
| <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) | |
| <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8) | |

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | |
|------------------------|-----|----|---|-----------------|
| Surface Water Present? | Yes | No | X | Depth (inches): |
| Water Table Present? | Yes | No | X | Depth (inches): |
| Saturation Present? | Yes | No | X | Depth (inches): |

(includes capillary fringe)

Wetland Hydrology Present? Yes No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:
Negative reaction to alpha, alpha-dipyridyl reagent. No dry season water table present. Sample plot elevation 2 feet higher than floodplain

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP12
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Terrace Local Relief (concave, convex, none): Concave Slope(%) 2.5% to
 Subregion (LRR): A Lat: 45.395324 Long: -122.613130 Datum: NAD83

Soil Map Unit Name: Cove silty clay loam NWI Classification: None
 Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | | |
|---------------------------------|-----|-------------------------------------|----|-------------------------------------|--|-----|--|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | | | | |
| Hydric Soil Present? | Yes | | No | <input checked="" type="checkbox"/> | Is the Sampled Area within a Wetland? | | |
| Wetland Hydrology Present? | Yes | | No | <input checked="" type="checkbox"/> | | Yes | No <input checked="" type="checkbox"/> X |

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

VEGETATION-- Use scientific names of plants.

Tree Stratum (Plot size: 30 Ft)

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|---------------------|-------------------------|-------------------------|-------------------------|
| Fraxinus latifolia | 45 | Y | FACW |
| Populus balsamifera | 10 | N | FAC |
| | 55 | =Total Cover | |

Shrub Stratum (Plot size: 30 Ft)

| | | | |
|--------------------|----|--------------|------|
| Corylus cornuta | 3 | Y | FACU |
| Rosa woodsii | 3 | Y | FACU |
| Crataegus monogyna | 2 | N | FAC |
| Salix scouleriana | 2 | N | FAC |
| Spiraea douglasii | 2 | N | FACW |
| | 12 | =Total Cover | |

Herb Stratum (Plot size: 6 Ft)

| | | | |
|----------------------|-----|--------------|------|
| Phalaris arundinacea | 75 | Y | FACW |
| Equisetum arvense | 40 | Y | FAC |
| Lapsana communis | 15 | N | FACU |
| Equisetum hyemale | 3 | N | FACW |
| Galium aparine | 1 | N | FACU |
| Ranunculus spp. | 1 | N | FAC |
| Vicia americana | 1 | N | FAC |
| | 136 | =Total Cover | |

Vine Stratum

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 3 | (A) |
| Total Number of Dominant Species Across all Strata: | 5 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 60.0% | (A/B) |

Prevalence Index Worksheet:

| | Total % Cover of: | Multiply by: | |
|--------------------------------|-------------------|--------------|---------|
| OBL species | 0 | x 1 = | 0 |
| FACW species | 125 | x 2 = | 250 |
| FAC species | 55 | x 3 = | 165 |
| FACU species | 22 | x 4 = | 88 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 202 | (A) | 503 (B) |
| <i>Prevalence Index = B/A=</i> | | | 2.49 |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation
 X Dominance Test > 50%
 X Prevalence Index ≤ 3.0
 Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)
 Problematic Hydrophytic Vegetation (Explain)
 Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

| | | | |
|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No |
|--|-----|-------------------------------------|----|

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|----------------|---|--------|-------|-----------|---------------------------|
| | Color (moist) | % | Color (moist) | % | Type 1 | Loc 2 | | |
| 0 to 16 | 10YR | 3 / 3 | 100 | | | | SILT LOAM | Uniform, dry fill materia |

¹Type: C=Concentration, D=Depletion, RM=Reduced Martix, CS=Covered or Coated Sand Grains.

²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type:
Depth (inches):

Hydric Soil Present? Yes No **X**

Remarks:
Soils have large pockets of fill material.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

Surface Water Present? Yes No X Depth (inches):
 Water Table Present? Yes No X Depth (inches):
 Saturation Present? Yes No X Depth (inches):

(includes capillary fringe)

Wetland Hydrology Present? Yes No **X**

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:
Due to lack of native soils, did not dig to 24".

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP13
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Terrace Local Relief (concave, convex, none): Concave Slope(%) 1.5% to

Subregion (LRR): A Lat: 45.393648 Long: -122.612152 Datum: NAD83

Soil Map Unit Name: Woodburn silt loam, 3 to 8 percent slopes NWI Classification: PEM1C

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)

Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No

Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | |
|---------------------------------|-----|-------------------------------------|--|--|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | |
| Hydric Soil Present? | Yes | | No | <input checked="" type="checkbox"/> |
| Wetland Hydrology Present? | Yes | | No | <input checked="" type="checkbox"/> |
| | | | Is the Sampled Area within a Wetland? | Yes No <input checked="" type="checkbox"/> |

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

VEGETATION-- Use scientific names of plants.

Tree Stratum

Shrub Stratum (Plot size: 30 Ft)

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|-------------------|-------------------------|-------------------------|-------------------------|
| Salix scouleriana | 25 | Y | FAC |
| | 25 | =Total Cover | |

Herb Stratum (Plot size: 6 Ft)

| | | | |
|---------------------------|----|--------------|------|
| Holcus lanatus | 40 | Y | FAC |
| Poa pratensis | 10 | N | FAC |
| Ranunculus repens | 7 | N | FAC |
| polygonatum lapathifolium | 5 | N | FACU |
| Lolium perenne | 3 | N | FAC |
| Lotus corniculatus | 3 | N | FAC |
| Rumex crispus | 1 | N | FAC |
| Vicia americana | 1 | N | FAC |
| | 70 | =Total Cover | |

Vine Stratum (Plot size: 30 Ft)

| | | | |
|------------------|----|--------------|------|
| Rubus armeniacus | 65 | Y | FACU |
| | 65 | =Total Cover | |

Dominance Test Worksheet:

| | | |
|---|-------|-------|
| Number of Dominant Species That Are OBL, FACW, or FAC: | 2 | (A) |
| Total Number of Dominant Species Across all Strata: | 3 | (B) |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 66.7% | (A/B) |

Prevalence Index Worksheet:

| Total % Cover of: | | Multiply by: | |
|--------------------------------|-----|--------------|---------|
| OBL species | 0 | x 1 = | 0 |
| FACW species | 0 | x 2 = | 0 |
| FAC species | 90 | x 3 = | 270 |
| FACU species | 70 | x 4 = | 280 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 160 | (A) | 550 (B) |
| <i>Prevalence Index = B/A=</i> | | | 3.44 |

Hydrophytic Vegetation Indicators:

Rapid Test for Hydrophytic Vegetation
 X Dominance Test > 50%
 Prevalence Index ≤ 3.0
 Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)
 Problematic Hydrophytic Vegetation (Explain)
 Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Hydrophytic Vegetation Present? Yes No

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|----------------|---------|-------------------|------------------|-----------------|-----------------|
| | Color (moist) | | Color (moist) | % | Type ¹ | Loc ² | | |
| 0 to 6 | 10YR | 2 / 2 | 100 | | | | SILTY CLAY LOAM | |
| 6 to 9 | 10YR | 2 / 2 | 99 | 5YR 5/6 | 1 | C | M | SILTY CLAY LOAM |
| 9 to 18 | 10YR | 2 / 2 | 100 | | | | | SILTY CLAY LOAM |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? **Yes** **No** **X**

Remarks:
Soils dry. No signs of saturation or moisture at 18"; assumed no dry season water table.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag. (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

Surface Water Present? Yes No X Depth (inches): _____
Water Table Present? Yes No X Depth (inches): _____
Saturation Present? Yes No X Depth (inches): _____
(includes capillary fringe)

Wetland Hydrology Present? **Yes** **No** **X**

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:
No signs of saturation or moisture at 18"; assumed no dry season water table.

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP14
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E
 Landform (hillslope, terrace, etc.): Floodplain Local Relief (concave, convex, none): Concave Slope(%) 2% to N
 Subregion (LRR): A Lat: 45.393830 Long: -122.612522 Datum: NAD83

Soil Map Unit Name: Woodburn silt loam, 3 to 8 percent slopes NWI Classification: None
 Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)
 Are Vegetation, Soil, Hydrology significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation, Soil, Hydrology naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | |
|---------------------------------|-----|-------------------------------------|----|-------------------------------------|--|--|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | | | |
| Hydric Soil Present? | Yes | | No | <input checked="" type="checkbox"/> | Is the Sampled Area within a Wetland? | |
| Wetland Hydrology Present? | Yes | | No | <input checked="" type="checkbox"/> | Yes | No <input checked="" type="checkbox"/> |

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

VEGETATION— Use scientific names of plants.

| | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> |
|--|-------------------------|-------------------------|-------------------------|
| <u>Tree Stratum</u> | | | |
| <u>Shrub Stratum</u> (Plot size: 30 Ft) | | | |
| Fraxinus latifolia | 3 | Y | FACW |
| | 3 | =Total Cover | |
| <u>Herb Stratum</u> (Plot size: 6 Ft) | | | |
| Holcus lanatus | 75 | Y | FAC |
| Lotus corniculatus | 70 | Y | FAC |
| Vicia americana | 10 | N | FAC |
| Juncus effusus | 5 | N | FACW |
| | 160 | =Total Cover | |
| <u>Vine Stratum</u> (Plot size: 30 Ft) | | | |
| Rubus armeniacus | 5 | Y | FACU |
| | 5 | =Total Cover | |

| | | | |
|---|-------|--------------|---------|
| Dominance Test Worksheet: | | | |
| Number of Dominant Species That Are OBL, FACW, or FAC: | 3 | (A) | |
| Total Number of Dominant Species Across all Strata: | 4 | (B) | |
| Percent of Dominant Species That Are OBL, FACW, or FAC: | 75.0% | (A/B) | |
| Prevalence Index Worksheet: | | | |
| Total % Cover of: | | Multiply by: | |
| OBL species | 0 | x 1 = | 0 |
| FACW species | 8 | x 2 = | 16 |
| FAC species | 155 | x 3 = | 465 |
| FACU species | 5 | x 4 = | 20 |
| UPL species | 0 | x 5 = | 0 |
| Column Totals: | 168 | (A) | 501 (B) |
| <i>Prevalence Index = B/A=</i> | | | 2.98 |

Hydrophytic Vegetation Indicators:
 Rapid Test for Hydrophytic Vegetation
 X Dominance Test > 50%
 X Prevalence Index ≤ 3.0
 Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet)
 Problematic Hydrophytic Vegetation (Explain)
 Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

% Bare Ground in Herb Stratum 0

| | | | |
|--|-----|-------------------------------------|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No |
|--|-----|-------------------------------------|----|

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|----------------|-----|-------------------|------------------|-----------|----------------------|
| | Color (moist) | | Color (moist) | % | Type ¹ | Loc ² | | |
| 0 to 12 | 10YR | 2 / 2 | | 100 | | | CLAY LOAM | |
| 12 to 16 | 10YR | 4 / 1 | 5YR 4/6 | 5 | D | M,PL | CLAY LOAM | Depleted, light grey |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Loamy Mucky Mineral (F1) (except MLRA 1)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)

Indicators for Problematic Hydric Soils:³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: _____
Depth (inches): _____

Hydric Soil Present? Yes No **X**

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- Surface Water (A1)
- High Water Table (A2)
- Saturation (A3)
- Water Marks (B1)
- Sediment Deposits (B2)
- Drift Deposits (B3)
- Algal Mat or Crust (B4)
- Iron Deposits (B5)
- Surface Soil Cracks (B6)
- Inundation Visible on Aerial Imagery (B7)
- Sparsely Vegetated Concave Surface (B8)
- Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B)
- Salt Crust (B11)
- Aquatic Invertebrates (B13)
- Hydrogen Sulfide Odor (C1)
- Oxidized Rhizospheres along Living Roots (C3)
- Presence of Reduced Iron (C4)
- Recent Iron Reduction in Tilled Soils (C6)
- Stunted or Stressed Plants (D1) (LRR A)
- Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag. (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

Surface Water Present? Yes No X Depth (inches): _____
 Water Table Present? Yes No X Depth (inches): _____
 Saturation Present? Yes No X Depth (inches): _____

(includes capillary fringe)

Wetland Hydrology Present? Yes No **X**

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

D2 - adjacent to floodplain

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Boardman Creek City/County: Clackamas County Sampling Date: 6/24/2016
 Applicant/Owner: OLSD State: OR Sampling Point: SP15
 Investigators: Irina Lapina Jennifer Maze Section, Township, Range S 18 T 2S R 2E

Surface Form (hillslope, terrace, etc.): Slope Local Relief (concave, convex, none): Concave Slope(%) 3 to E
 Subregion (LRR): A Lat: 45.393875 Long: -122.612440 Datum: NAD83

Soil Map Unit Name: Woodburn silt loam, 3 to 8 percent slopes NWI Classification: None

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If No, explain in Remarks)

Are Vegetation, Soil, Hydrology, significantly disturbed? Are "Normal Circumstances" present? Yes No

Are Vegetation, Soil, Hydrology, naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS - Attach a site map showing sampling point locations, transects, important features, etc.

| | | | | | | |
|---------------------------------|-----|-------------------------------------|----|--|-----|----|
| Hydrophytic Vegetation Present? | Yes | <input checked="" type="checkbox"/> | No | | | |
| Hydric Soil Present? | Yes | <input checked="" type="checkbox"/> | No | Is the Sampled Area within a Wetland? | | |
| Wetland Hydrology Present? | Yes | <input checked="" type="checkbox"/> | No | | Yes | No |

Remarks:
 Cloudy, 56-67 deg F, 0.3in precip.

| VEGETATION — Use scientific names of plants. | <u>Absolute % Cover</u> | <u>Dominant Species</u> | <u>Indicator Status</u> | Dominance Test Worksheet: | | |
|---|-------------------------|-------------------------|-------------------------|---|-------------------------------------|-------------|
| <u>Tree Stratum</u> (Plot size: 30 Ft) | | | | Number of Dominant Species That Are OBL, FACW, or FAC: | 2 | (A) |
| Fraxinus latifolia | 5 | Y | FACW | Total Number of Dominant Species Across all Strata: | 2 | (B) |
| | 5 | =Total Cover | | Percent of Dominant Species That Are OBL, FACW, or FAC: | 100.0% | (A/B) |
| <u>Shrub Stratum</u> | | | | Prevalence Index Worksheet: | | |
| <u>Herb Stratum</u> (Plot size: 10 Ft) | | | | Total % Cover of: | Multiply by: | |
| Scirpus microcarpus | 85 | Y | OBL | OBL species | 85 | x 1 = 85 |
| Phalaris arundinacea | 5 | N | FACW | FACW species | 12 | x 2 = 24 |
| Juncus effusus | 2 | N | FACW | FAC species | 2 | x 3 = 6 |
| Lotus corniculatus | 2 | N | FAC | FACU species | 0 | x 4 = 0 |
| | 94 | =Total Cover | | UPL species | 0 | x 5 = 0 |
| <u>Vine Stratum</u> | | | | Column Totals: | 99 | (A) 115 (B) |
| | | | | Prevalence Index = B/A= 1.16 | | |
| | | | | Hydrophytic Vegetation Indicators: | | |
| | | | | X Rapid Test for Hydrophytic Vegetation | | |
| | | | | X Dominance Test > 50% | | |
| | | | | X Prevalence Index ≤ 3.0 | | |
| | | | | Morphological Adaptations (Provide supporting data in Remarks or on a separate sheet) | | |
| | | | | Problematic Hydrophytic Vegetation (Explain) | | |
| | | | | Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic. | | |
| | | | | Hydrophytic Vegetation Present? | | |
| | | | | Yes | <input checked="" type="checkbox"/> | No |

% Bare Ground in Herb Stratum 0

Remarks: (Include photo numbers here or on a separate sheet.)

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of Indicators.)

| Depth (inches) | Matrix | | | Redox Features | | | | Texture | Remarks |
|----------------|---------------|-------|-----|----------------|---|---|--------|-----------|---------|
| | Color (moist) | | % | Color (moist) | | % | Type 1 | | |
| 0 to 12 | 10YR | 2 / 2 | 100 | | | | | CLAY LOAM | |
| 12 to 16 | 10YR | 4 / 1 | 95 | 5YR 4/6 | 5 | D | M | CLAY LOAM | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Martix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol (A1) | <input type="checkbox"/> Sandy Redox (S5) |
| <input type="checkbox"/> Histic Epipedon (A2) | <input type="checkbox"/> Stripped Matrix (S6) |
| <input type="checkbox"/> Black Histic (A3) | <input type="checkbox"/> Loamy Mucky Mineral (F1) (except MLRA 1) |
| <input checked="" type="checkbox"/> Hydrogen Sulfide (A4) | <input type="checkbox"/> Loamy Gleyed Matrix (F2) |
| <input type="checkbox"/> Depleted Below Dark Surface (A11) | <input type="checkbox"/> Depleted Matrix (F3) |
| <input type="checkbox"/> Thick Dark Surface (A12) | <input type="checkbox"/> Redox Dark Surface (F6) |
| <input type="checkbox"/> Sandy Mucky Mineral (S1) | <input type="checkbox"/> Depleted Dark Surface (F7) |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4) | <input type="checkbox"/> Redox Depressions (F8) |

Indicators for Problematic Hydric Soils: ³

- 2 cm Muck (A10)
- Red Parent Material (TF2)
- Very Shallow Dark Surface (TF12)
- Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type:
Depth (inches):

Hydric Soil Present? Yes X No

Remarks:
Saturated soils.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- | | |
|--|--|
| <input type="checkbox"/> Surface Water (A1) | <input type="checkbox"/> Water-Stained Leaves (B9) (except MLRA 1, 2, 4A and 4B) |
| <input type="checkbox"/> High Water Table (A2) | <input type="checkbox"/> Salt Crust (B11) |
| <input checked="" type="checkbox"/> Saturation (A3) | <input type="checkbox"/> Aquatic Invertebrates (B13) |
| <input type="checkbox"/> Water Marks (B1) | <input type="checkbox"/> Hydrogen Sulfide Odor (C1) |
| <input type="checkbox"/> Sediment Deposits (B2) | <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) |
| <input type="checkbox"/> Drift Deposits (B3) | <input type="checkbox"/> Presence of Reduced Iron (C4) |
| <input type="checkbox"/> Algal Mat or Crust (B4) | <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) |
| <input type="checkbox"/> Iron Deposits (B5) | <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) |
| <input type="checkbox"/> Surface Soil Cracks (B6) | <input type="checkbox"/> Other (Explain in Remarks) |
| <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) | |
| <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8) | |

Secondary Indicators (minimum of two required)

- Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B)
- Drainage Patterns (B10)
- Dry-Season Water Table (C2)
- Saturation Visible on Aerial Imag (C9)
- Geomorphic Position (D2)
- Shallow Aquitard (D3)
- FAC-Neutral Test (D5)
- Paired Ant Mounds (D6) (LRR A)
- Frost-Heave Hummocks (D7)

Field Observations:

| | | | | | |
|------------------------|-----|----|----|-----------------|----|
| Surface Water Present? | Yes | No | X | Depth (inches): | |
| Water Table Present? | Yes | X | No | Depth (inches): | 16 |
| Saturation Present? | Yes | X | No | Depth (inches): | 0 |

(includes capillary fringe)

Wetland Hydrology Present? Yes X No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks: